





# LOAN DOCUMENT

		PHOTOGRAPH THIS SHEET				
DTIC ACCESSION NUMBER		LEVEL				
	<u>Bioventing Field Initiative at Galena...</u> DOCUMENT IDENTIFICATION 23 Apr 93					
					DISTRIBUTION STATEMENT A Approved for Public Release Distribution Unlimited	
	ACCESSION FOR					
NTIS <input type="checkbox"/> GRA&I <input type="checkbox"/>						
DTIC <input type="checkbox"/> TRAC <input type="checkbox"/>						
UNANNOUNCED <input type="checkbox"/>						
JUSTIFICATION <input type="checkbox"/>						
BY						
DISTRIBUTION/						
AVAILABILITY CODES						
DISTRIBUTION						
AVAILABILITY AND/OR SPECIAL						
A-1		DATE ACCESSIONED		CARE		
DISTRIBUTION STAMP						
		DATE RETURNED				
20001226 021		REGISTERED OR CERTIFIED NUMBER				
DATE RECEIVED IN DTIC		PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-FDAC				

H  
A  
N  
D  
L  
E  
  
W  
I  
T  
H  
  
C  
A  
R  
E

**INTERIM REPORT**

**April 23, 1993**

**FOR**

**BIOVENTING FIELD INITIATIVE**

**AT**

**GALENA AND CAMPION AIR FORCE STATIONS, ALASKA**

**to**

**Captain Catherine M. Vogel  
Department of the Air Force  
AL/EQ  
139 Barnes Drive  
Tyndall AFB, Florida 32403-5319**

**by**

**BATTELLE  
Columbus Operations  
505 King Avenue  
Columbus, Ohio 43201-2693**

*AQM01-03-0577*

**DEFENSE TECHNICAL INFORMATION CENTER  
REQUEST FOR SCIENTIFIC AND TECHNICAL REPORTS**Title AFCEE Collection**1. Report Availability (Please check one box)**

- ☒ This report is available. Complete sections 2a - 2f.  
☐ This report is not available. Complete section 3.

**2a. Number of  
Copies Forwarded**1 each**2b. Forwarding Date**July/2000**2c. Distribution Statement (Please check ONE box)**

DoD Directive 5230.24, "Distribution Statements on Technical Documents," 18 Mar 87, contains seven distribution statements, as described briefly below. Technical documents MUST be assigned a distribution statement.

- ☒ DISTRIBUTION STATEMENT A: Approved for public release. Distribution is unlimited.
- ☐ DISTRIBUTION STATEMENT B: Distribution authorized to U.S. Government Agencies only.
- ☐ DISTRIBUTION STATEMENT C: Distribution authorized to U.S. Government Agencies and their contractors.
- ☐ DISTRIBUTION STATEMENT D: Distribution authorized to U.S. Department of Defense (DoD) and U.S. DoD contractors only.
- ☐ DISTRIBUTION STATEMENT E: Distribution authorized to U.S. Department of Defense (DoD) components only.
- ☐ DISTRIBUTION STATEMENT F: Further dissemination only as directed by the controlling DoD office indicated below or by higher authority.
- ☐ DISTRIBUTION STATEMENT X: Distribution authorized to U.S. Government agencies and private individuals or enterprises eligible to obtain export-controlled technical data in accordance with DoD Directive 5230.25, Withholding of Unclassified Technical Data from Public Disclosure, 6 Nov 84.

**2d. Reason For the Above Distribution Statement (in accordance with DoD Directive 5230.24)****2e. Controlling Office**HQ AFCEE**2f. Date of Distribution Statement  
Determination**15 Nov 2000**3. This report is NOT forwarded for the following reasons. (Please check appropriate box)**

- ☐ It was previously forwarded to DTIC on \_\_\_\_\_ (date) and the AD number is \_\_\_\_\_
- ☐ It will be published at a later date. Enter approximate date if known. \_\_\_\_\_
- ☐ In accordance with the provisions of DoD Directive 3200.12, the requested document is not supplied because: \_\_\_\_\_

**Print or Type Name**Laura Peña**Signature**Laura Peña**Telephone**210-536-1431

(For DTIC Use Only)

AQ Number MD1-03-0577

## TABLE OF CONTENTS

LIST OF TABLES .....	iii
LIST OF FIGURES .....	iii
1.0 INTRODUCTION .....	1
1.1 Objectives .....	1
1.2 Site Description .....	2
1.2.1 Saddle Tank Farm Site (Galena) .....	2
1.2.2 Power Plant Site (Galena) .....	4
1.2.3 Million Gallon Hill Site (Galena) .....	4
1.2.4 Petroleum, Oil, and Lubricants (POL) Tank Site 1 (Campion) .....	4
2.0 SADDLE TANK FARM SITE .....	4
2.1 Chronology of Events and Site Activities .....	4
2.1.1 Groundwater Measurements .....	4
2.1.2 Soil Gas Survey .....	8
2.1.3 Vent Well, Monitoring Point, and Thermocouple Installation .....	8
2.1.4 Soil and Soil Gas Sampling and Analyses .....	11
2.1.5 Soil Gas Permeability and Radius of Influence .....	11
2.1.6 In Situ Respiration Test .....	12
2.2 Results and Discussion .....	13
2.2.1 Soil and Soil Gas Analyses .....	13
2.2.2 Soil Gas Permeability and Radius of Influence .....	13
2.2.3 In Situ Respiration Test .....	16
2.2.4 Bioventing Demonstration .....	16
3.0 POWER PLANT SITE .....	20
3.1 Chronology of Events and Site Activities .....	20
3.1.1 Groundwater Measurements .....	20
3.1.2 Soil Gas Survey .....	20
3.1.3 Vent Well, Monitoring Point, and Thermocouple Installation .....	20
3.1.4 Soil and Soil Gas Sampling and Analyses .....	24
3.1.5 Soil Gas Permeability and Radius of Influence .....	25
3.1.6 In Situ Respiration Test .....	25
3.2 Results and Discussion .....	26
3.2.1 Soil and Soil Gas Analyses .....	26
3.2.3 In Situ Respiration Test .....	26
3.2.4 Bioventing Demonstration .....	31
4.0 MILLION GALLON HILL SITE .....	32
4.1 Chronology of Events and Site Activities .....	32
4.1.1 Groundwater Measurements .....	32
4.1.2 Soil Gas Survey .....	32
4.1.3 Vent Well, Monitoring Point, and Thermocouple Installation .....	32
4.1.4 Soil Gas Sampling and Analyses .....	35

4.1.5	Soil Gas Permeability and Radius of Influence . . . . .	35
4.1.6	In Situ Respiration Test . . . . .	36
4.2	Results and Discussion . . . . .	36
4.2.1	Soil Gas Analyses . . . . .	36
4.2.2	Soil Gas Permeability and Radius of Influence . . . . .	36
4.2.3	In Situ Respiration Test . . . . .	39
4.2.4	Bioventing Demonstration . . . . .	39
5.0	CAMPION POL TANK SITE . . . . .	41
5.1	Chronology of Events and Site Activities . . . . .	41
5.1.1	Groundwater Measurements . . . . .	41
5.1.2	Soil Gas Survey . . . . .	41
5.1.3	Vent Well, Monitoring Point, and Thermocouple Installation . . . . .	41
5.1.4	Soil and Soil Gas Sampling and Analyses . . . . .	44
5.1.5	Soil Gas Permeability and Radius of Influence . . . . .	44
5.1.6	In Situ Respiration Test . . . . .	45
5.2	Results and Discussion . . . . .	45
5.2.1	Soil and Soil Gas Analyses . . . . .	45
5.2.2	Soil Gas Permeability and Radius of Influence . . . . .	45
5.2.3	In Situ Respiration Test . . . . .	49
5.2.4	Bioventing Demonstration . . . . .	49
6.0	BACKGROUND AREA . . . . .	51
7.0	FUTURE WORK . . . . .	51
8.0	REFERENCE . . . . .	53
APPENDIX A: TEST PLAN FOR GALENA AND CAMPION AFS, ALASKA . . . . .		A-1
APPENDIX B: ANALYTICAL REPORT FOR THE SADDLE TANK FARM SITE, THE POWER PLANT SITE, THE MILLION GALLON HILL SITE, AND THE CAMPION POL TANK SITE . . . . .		B-1
APPENDIX C: SADDLE TANK FARM SITE SOIL GAS PERMEABILITY DATA . . . . .		C-1
APPENDIX D: SADDLE TANK FARM SITE IN SITU RESPIRATION TEST DATA . . . . .		D-1
APPENDIX E: POWER PLANT SITE SOIL GAS PERMEABILITY DATA . . . . .		E-1
APPENDIX F: POWER PLANT SITE IN SITU RESPIRATION TEST DATA . . . . .		F-1
APPENDIX G: MILLION GALLON HILL SITE SOIL GAS PERMEABILITY DATA . . . . .		G-1
APPENDIX H: MILLION GALLON HILL SITE IN SITU RESPIRATION TEST DATA . . . . .		H-1
APPENDIX I: CAMPION POL TANK SITE SOIL GAS PERMEABILITY DATA . . . . .		I-1
APPENDIX J: CAMPION POL TANK SITE IN SITU RESPIRATION TEST DATA . . . . .		J-1

## LIST OF TABLES

Table 1.	Initial Soil Gas Composition at the Saddle Tank Farm Site . . . . .	9
Table 2.	Results From Soil and Soil Gas Analyses for BTEX and TPH at the Saddle Tank Farm Site . . . . .	14
Table 3.	Results From Soil Chemistry Analyses at the Saddle Tank Farm Site . . . . .	14
Table 4.	Results of Hyperventilate™ Soil Gas Permeability Analysis at the Saddle Tank Farm Site . . . . .	15
Table 5.	Oxygen Utilization and Carbon Dioxide Production Rates During the In Situ Respiration Test at the Saddle Tank Farm Site . . . . .	19
Table 6.	Initial Soil Gas Composition at the Power Plant Site . . . . .	21
Table 7.	Results From Soil and Soil Gas Analyses for BTEX and TPH at the Power Plant Site . . . . .	27
Table 8.	Results From Soil Chemistry Analyses at the Power Plant Site . . . . .	27
Table 9.	Results of Hyperventilate™ Soil Gas Permeability Analysis at the Power Plant Site . . . . .	28
Table 10.	Oxygen Utilization and Carbon Dioxide Production Rates During the In Situ Respiration Test at the Power Plant Site . . . . .	31
Table 11.	Initial Soil Gas Composition at the Million Gallon Hill Site . . . . .	33
Table 12.	Results From Soil Gas Analyses for BTEX and TPH at the Million Gallon Hill Site . . . . .	37
Table 13.	Results of Hyperventilate™ Soil Gas Permeability Analysis at the Million Gallon Hill Site . . . . .	37
Table 14.	Oxygen Utilization and Carbon Dioxide Production Rates During the In Situ Respiration Test at the Million Gallon Hill Site . . . . .	39
Table 15.	Initial Soil Gas Composition at the Campion POL Tank Site . . . . .	42
Table 16.	Results From Soil and Soil Gas Analyses for BTEX and TPH at the Campion POL Tank Site . . . . .	46
Table 17.	Results From Soil Chemistry Analyses at the Campion POL Tank Site . . . . .	47
Table 18.	Results of Hyperventilate™ Soil Gas Permeability Analysis at the Campion POL Tank Site . . . . .	47
Table 19.	Oxygen Utilization and Carbon Dioxide Production Rates During the In Situ Respiration Test at the Campion POL Tank Site . . . . .	49

## LIST OF FIGURES

Figure 1.	Schematic Diagram of Saddle Tank Farm Site at Galena AFS (GS - Soil Gas Survey Point; MP - Monitoring Point) . . . . .	3
Figure 2.	Schematic Diagram of Power Plant Site at Galena AFS (GS - Soil Gas Survey Point; MP - Monitoring Point) . . . . .	5
Figure 3.	Schematic Diagram of Million Gallon Hill Site at Galena AFS (GS - Soil Gas Survey Point; MP - Monitoring Point) . . . . .	6
Figure 4.	Schematic Diagram of POL Tank Site at Campion AFS (GS - Soil Gas Survey Point; MP - Monitoring Point) . . . . .	7
Figure 5.	Cross Section of Vent Well and Monitoring Points at the Saddle Tank Farm Site Showing Site Lithology and Construction Detail (not to scale) . . . . .	10
Figure 6.	Radius of Influence at the Saddle Tank Farm Site . . . . .	17

Figure 7.	Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G1-MPA-4.0' at the Saddle Tank Farm Site . . .	18
Figure 8.	Cross Section of Vent Well and Monitoring Points at the Power Plant Site Showing Site Lithology and Construction Detail (not to scale) . . . . .	22
Figure 9.	Cross Section of Vent Well and Monitoring Points at the Power Plant Site Showing Elevation Differences . . . . .	23
Figure 10.	Radius of Influence at the Power Plant Site . . . . .	29
Figure 11.	Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G2-MPB-8.0' at the Power Plant Site . . . . .	30
Figure 12.	Cross Section of Vent Well and Monitoring Points at the Million Gallon Hill Site Showing Site Lithology and Construction Detail (not to scale) . . . . .	34
Figure 13.	Radius of Influence at the Million Gallon Hill Site . . . . .	38
Figure 14.	Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G3-MPA-27.5' at the Million Gallon Hill Site . . . . .	40
Figure 15.	Cross Section of Vent Well and Monitoring Points at the Campion POL Tank Site Showing Site Lithology and Construction Detail (not to scale) . . . . .	43
Figure 16.	Radius of Influence at the Campion POL Tank Site . . . . .	48
Figure 17.	Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point C1-MPC-5.0' at the Campion POL Tank Site . . . . .	50
Figure 18.	Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at the Background Area . . . . .	52

**INTERIM REPORT**  
**BIOVENTING FIELD INITIATIVE**  
**GALENA AND CAMPION AIR FORCE STATIONS, ALASKA**

**1.0 INTRODUCTION**

This report describes the activities conducted at Galena Air Force Station (AFS) and Campion AFS, Alaska, as part of the Bioventing Field Initiative for the U.S. Air Force Center for Environmental Excellence (AFCEE) and the Environmental Quality Directorate of the Air Force Armstrong Laboratory. This report summarizes the results from the first phase of the study at Galena AFS and Campion AFS. First-phase activities include a soil gas survey, air permeability test, in situ respiration tests, and installation of bioventing systems. The specific objectives of this Bioventing Field Initiative are described in the following section. Each site at the base is discussed individually, followed by a description of site activities at the background area.

**1.1 Objectives**

The purpose of this Bioventing Field Initiative is to measure the soil gas permeability and microbial activity at a contaminated site in order to evaluate the potential application of bioventing technology to remediate the site. The specific test objectives are stated below.

- A small-scale soil gas survey will be conducted to identify an appropriate location for installation of the bioventing system. Soil gas from the candidate site should exhibit high total petroleum hydrocarbon (TPH) concentrations, relatively low oxygen concentrations, and relatively high carbon dioxide concentrations. An uncontaminated background location also will be identified.
- The soil gas permeability of the soil and the air vent (well) radius of influence will be determined. To measure these parameters, air will be withdrawn or injected for approximately 8 hours at vent wells located in contaminated soils. Pressure changes will be monitored in an array of monitoring points.
- Immediately following the soil gas permeability test, an in situ respiration test will be conducted. Air will be injected into selected monitoring points to



aerate the soils. The in situ oxygen utilization and carbon dioxide production rates will be measured.

- The data from the soil gas permeability and in situ respiration tests will be used to determine an air injection/withdrawal rate for the bioventing test. A blower will be selected, installed, and operated for 6 to 12 months, and periodic measurements of the soil gas composition will be made to evaluate the long-term effectiveness of bioventing.

## **1.2 Site Description**


Galena AFS is located approximately 280 miles west of Fairbanks, Alaska, on the Yukon River. The installation is a forward operating base of the U.S. Air Force Alaska Air Command. Approximately 350 military personnel currently are assigned to the base. The population of the adjacent community of Galena is approximately 750. Galena is not connected by road to any other community and is accessible only by air or water.

Campion AFS, located approximately 12 miles east of Galena, was deactivated and demolished in the early to mid-1980s. The site is accessible by gravel road from Galena AFS. No buildings remain, and electrical power currently cannot be accessed at the site.

Descriptions of the sites at Galena and Campion AFS are given in the following sections. A detailed description is provided in the Test Plan in Appendix A.

### **1.2.1 Saddle Tank Farm Site (Galena)**

The Saddle Tank Farm Site is located east of tanks 37 and 38. The tank farm contains approximately 20 aboveground petroleum storage tanks in a diked area (Figure 1). Groundwater at the site typically is encountered at less than 10 feet beneath the surface, although measurements taken during system installation showed depths of 15 to 17 feet. This site is located several hundred feet from a vapor extraction pilot study being conducted by Radian Corporation. Soil analytical data have not been made available for this site.



**Figure 1. Schematic Diagram of Saddle Tank Farm Site at Galena AFS (GS - Soil Gas Survey Point; MP - Monitoring Point)**

### **1.2.2 Power Plant Site (Galena)**

The Power Plant Site is a 20,000-gallon diesel tank located adjacent to the base power plant (Figure 2). Groundwater is encountered at approximately 10 feet beneath the surface at the site. Soil analytical data have indicated TPH concentrations in excess of 10,000 ppm.

### **1.2.3 Million Gallon Hill Site (Galena)**

Tanks 37 and 38 are large-capacity aboveground petroleum storage tanks containing diesel fuel and JP-4 jet fuel, respectively (Figure 3). The tanks are located in a fuel storage tank farm along with JP-4 jet fuel storage tanks 41 and 42. The tank farm is located on a fill mound built up approximately 30 feet above grade. Groundwater is located at approximately 40 feet below the tanks. Soil analytical data indicate that contamination is encountered primarily at depths greater than 20 feet.

### **1.2.4 Petroleum, Oil, and Lubricants (POL) Tank Site 1 (Campion)**


Campion POL Tank Site is located in the former petroleum storage tank farm at Campion AFS (Figure 4). The tanks have been removed, but their former location is evidenced by circular gravel pads inside a diked area. Soil samples from the site have indicated TPH concentrations of 300 to 500 mg/kg. Groundwater at the site is present at approximately 10 feet beneath the surface.

## **2.0 SADDLE TANK FARM SITE**


### **2.1 Chronology of Events and Site Activities**

#### **2.1.1 Groundwater Measurements**


Groundwater was measured at three wells: DTP, DTW, and DTB at the Saddle Tank Farm Site. The depths measured were 15.8 feet (Well DTP), 16.55 feet (Well DTW), and 30.26 feet (Well DTB).



**Figure 2. Schematic Diagram of Power Plant Site at Galena AFS (GS - Soil Gas Survey Point; MP - Monitoring Point)**



**Figure 3. Schematic Diagram of Million Gallon Hill Site at Galena AFS (GS - Soil Gas Survey Point; MP - Monitoring Point)**



**Figure 4. Schematic Diagram of POL Tank Site at Campion AFS (GS - Soil Gas Survey Point; MP - Monitoring Point)**

### 2.1.2 Soil Gas Survey

A suitable site for the bioventing demonstration should have soil gas characteristics of high TPH, low oxygen, and high carbon dioxide concentrations. This composition of soil gas would indicate that oxygen-limiting conditions for microbial activity are present and that the introduction of air may enhance biodegradation of TPH.

On August 17, 1992, a limited soil gas survey was conducted at the area recommended by the point-of-contact (POC) at the Saddle Tank Farm Site. Soil gases were sampled by driving a 5/8-inch-diameter stainless steel probe into the soil with a hammer drill. Soil gas was withdrawn with a vacuum pump and was analyzed for oxygen, carbon dioxide, and TPH.

Measurements of oxygen and carbon dioxide in the soil gas were made with a GasTech Model 32520X with oxygen and carbon dioxide ranges of 0 to 25%. The analyzer was calibrated daily against atmospheric oxygen, atmospheric carbon dioxide, a 10% oxygen calibration standard, and a 5% carbon dioxide calibration standard. TPH was measured with a GasTech Trace Techtor with TPH ranges from 0 to 100, 0 to 1,000, and 0 to 10,000 ppm. The GasTech Trace Techtor was calibrated daily against a 4,200-ppm hexane standard.

The soil gas probes were driven to depths ranging from 2.5 to 7.5 feet at several locations at the Saddle Tank Farm Site. Once groundwater was encountered, the probes were not driven deeper. Table 1 provides the initial concentrations of oxygen, carbon dioxide, and TPH for the various locations at the Saddle Tank Farm Site. Oxygen concentrations varied from 4.0 to 18.0%, and TPH concentrations ranged from 90 to 3,600 ppm. In general, the oxygen concentrations tended to decrease with increasing depth, whereas TPH tended to increase with increasing depth. The oxygen results indicate that some areas at this site are oxygen-limited and may respond to bioventing.

### 2.1.3 Vent Well, Monitoring Point, and Thermocouple Installation

On August 20, 1992, one vent well and three monitoring points were installed, and soil samples were collected for analyses at the Saddle Tank Farm Site. The monitoring points (MP) were labeled as follows: G1-MPA; G1-MPB; and G1-MPC. The locations of the vent well and monitoring points are shown in Figure 1. A cross section of the vent well and monitoring points showing site lithology and construction detail is shown in Figure 5.

**Table 1. Initial Soil Gas Composition at the Saddle Tank Farm Site**

<b>Monitoring Point</b>	<b>Depth (ft)</b>	<b>Oxygen (%)</b>	<b>Carbon Dioxide (%)</b>	<b>TPH (ppm)</b>
GS-1	2.5	16.5	4.1	90
	5.0	4.0	18.0	1,600
	7.5	5.0	10.0	3,600
GS-2	2.5	18.0	2.5	90
GS-3	2.5	3.0	9.0	90






Figure 5. Cross Section of Vent Well and Monitoring Points at the Saddle Tank Farm Site Showing Site Lithology and Construction Detail (not to scale)

The vent well was installed at a depth of 11.0 feet into a 6-inch-diameter borehole. The vent well consisted of Schedule 40 2-inch-diameter polyvinyl chloride (PVC) piping with 7.5 feet of ten-slot screen. The annular space corresponding to the screened area of the well was filled with silica sand, and the annular space above the screened interval was filled with bentonite to prevent short-circuiting of air to or from the surface.

Soil gas probes consisted of 1/4-inch tubing with a 1-inch-diameter, 6-inch screened area. The annular space corresponding to the screened area was filled with silica sand, whereas the interval between the screened areas was filled with bentonite, as was the annular space from the shallowest monitoring point to the ground surface. All monitoring points were installed at a depth of 11.0 feet into an 8-inch-diameter borehole and screened to three depths: 4.0, 7.5, and 11.0 feet.

A Type J thermocouple was installed with monitoring points G1-MPA-4.0' and G1-MPA-11.0'.

#### **2.1.4 Soil and Soil Gas Sampling and Analyses**

Soil samples were collected at the Saddle Tank Farm Site at depths of 2.5 to 3.0 feet, 5.5 to 6.0 feet, and 8.0 to 8.5 feet from the vent well borehole and were labeled GA1-V-2.5, GA1-V-5.5, and GA1-V-8.0, respectively. The samples were sent under chain of custody to Engineering-Science, Inc., Berkeley Laboratory for analyses of benzene, toluene, ethylbenzene, and xylenes (BTEX); TPH; alkalinity; moisture content; pH; iron; total phosphorous; and total Kjeldahl nitrogen.

Soil gas samples also were collected from the vent well and from monitoring points G1-MPA and G1-MPC, and these were labeled vent well, MPA red, and MPC red. These samples were sent under chain of custody to Air Toxics, Ltd., in Rancho Cordova, California, for analysis of BTEX and TPH.

#### **2.1.5 Soil Gas Permeability and Radius of Influence**

A detailed description of the method for conducting a soil gas permeability test, including equations to compute  $k$ , the soil gas permeability, is given in the Test Plan and Technical Protocol (Hinchee et al., 1992).

Prior to air injection at the Saddle Tank Farm Site, the monitoring points were allowed to set up for 96 hours. Air was injected with a portable 1-horsepower (HP) explosion-proof positive


displacement blower unit. After air injection was initiated, pressure readings were taken approximately every 1 to 2 minutes for the first hour, then approximately every 10 minutes for the following hour. The Hyperventilate™ computer model was used to calculate the soil gas permeability.

#### 2.1.6 In Situ Respiration Test

Immediately following the soil gas permeability test at the Saddle Tank Farm Site, air containing approximately 1% helium was injected into the soil for approximately 20 hours, beginning on August 25. Air was injected concurrently into the background monitoring well to measure the natural biodegradation of organic material in the soil. The setup for the in situ respiration test is described by the Test Plan and Technical Protocol (Hinchee et al., 1992). The pump used for air injection was a ½-HP diaphragm pump. Air and helium were injected through the following monitoring points at the depths indicated: G1-MPA-4.0'; G1-MPA-7.5'; G1-MPB-7.5'; and G1-MPC-11.0'. After the air/helium injection was turned off, the respiration gases were monitored periodically. The respiration test was terminated on August 28.

Helium concentrations were measured during the in situ respiration test to quantify helium leakage to or from the surface around the monitoring points. Helium loss over time is attributed to either diffusion or leakage. A rapid drop in helium concentration followed by a leveling is an indication of leakage. A gradual loss along with an apparent first-order curve is an indicator of diffusion. As a rough estimate, the diffusion of gas molecules is inversely proportional to the square root of the molecular weight of the gas. Based on molecular weights of 4 for helium and 32 for oxygen, helium gas diffuses about 2.8 times faster than oxygen, or the diffusion of oxygen is 0.35 times the rate of helium diffusion. As a general rule, we have found that if helium concentrations are at least 50% to 60% of the initial levels at test completion, measured oxygen uptake rates are representative. Greater helium loss indicates a problem, and oxygen utilization rates are not considered representative.

To compare data from one site to another, a stoichiometric relationship of the oxidation of the hydrocarbon was assumed. Hexane was used as the representative hydrocarbon for the organic contaminant. The stoichiometric relationship is given by:



Based on the utilization rates (% per day), the biodegradation rates in terms of mg as a hexane equivalent per kg of soil per day were computed using the equation below by assuming a soil porosity of 0.2 and a bulk density of 1,440 kg/m<sup>3</sup>.

$$K_p = \frac{-K_o A D_o C}{100} \quad (2)$$

where:  $K_p$  = biodegradation rate (mg/kg/day)  
 $K_o$  = oxygen utilization rate (percent per day)  
 $A$  = volume of air/kg of soil, in this case  $300/1,440 = 0.21$   
 $D_o$  = density of oxygen gas (mg/L) assumed to be 1,330 mg/L  
 $C$  = mass ratio of hydrocarbon to oxygen required for mineralization, assumed to be 1/3.5 from the above stoichiometric equation.

## 2.2 Results and Discussion

### 2.2.1 Soil and Soil Gas Analyses

Results of the soil analyses for BTEX and TPH at the Saddle Tank Farm Site are presented in Table 2. The analytical report for this site is presented in Appendix B. Concentrations of the BTEX compounds in soil samples ranged from below the detection limit (benzene and ethylbenzene) up to 3 mg/kg (total xylenes), whereas TPH concentrations ranged from 85 to 420 mg/kg. The soil gas analyses also showed similar measurements of BTEX and TPH, with concentrations of TPH ranging from 36 to 6,700 ppmv and from less than 0.11 ppmv (benzene) up to 120 ppmv (benzene) (Table 2). The results of the soil chemistry analyses are summarized in Table 3.

### 2.2.2 Soil Gas Permeability and Radius of Influence

The raw data for the soil gas permeability test at the Saddle Tank Farm Site are presented in Appendix C. Using the Hyperventilate™ computer model, soil gas permeabilities were calculated at each of the monitoring points. These data are presented in Table 4. The soil gas permeability varied

**Table 2. Results From Soil and Soil Gas Analyses for BTEX and TPH at the Saddle Tank Farm Site**

Matrix	Sample Name	Benzene (mg/kg)	Toluene (mg/kg)	Ethylbenzene (mg/kg)	Total Xylenes (mg/kg)	TPH <sup>1</sup> (mg/kg)
Soil	GA1-V-2.5	<0.075	1.0	<0.063	1.2	420
	GA1-V-5.5	<0.080	0.42	<0.066	3.0	300
	GA1-V-8.0	<0.076	0.48	<0.063	0.96	85
Matrix	Sample Name	Benzene (ppmv)	Toluene (ppmv)	Ethylbenzene (ppmv)	Total Xylenes (ppmv)	TPH <sup>2</sup> (ppmv)
Soil Gas	Vent well	0.3	0.084	0.034	0.12	36
	MPA red	120	22	6.8	18	6,700
	MPC red	<0.11	2.9	1.3	0.97	1,500

<sup>1</sup> Referenced to a reference oil composed of a mixture of 2,2,4-trimethylpentane, *n*-hexadecane, and chlorobenzene.

<sup>2</sup> TPH referenced to gasoline (molecular weight = 100).

**Table 3. Results From Soil Chemistry Analyses at the Saddle Tank Farm Site**

Parameter	Sample Name		
	GA1-V-2.5	GA1-V-5.5	GA1-V-8.0
Alkalinity (mg/kg CaCO <sub>3</sub> )	400	670	500
Moisture (% by weight)	20.3	24.8	20.7
pH	7.8	7.4	7.4
Iron (mg/kg)	20,300	24,500	19,500
Total Phosphorus (mg/kg)	670	720	790
Total Kjeldahl Nitrogen (mg/kg)	800	800	800

**Table 4. Results of Hyperventilate™ Soil Gas Permeability Analysis at the Saddle Tank Farm Site**

Monitoring Point	Depth (ft)	Soil Gas Permeability (darcy)
G1-MPA	4.0	$1.7 \times 10^9$
	7.5	$1.1 \times 10^9$
	11.0	$7.2 \times 10^8$
G1-MPB	4.0	1,500
	7.5	2,400
	11.0	18,000
G1-MPC	4.0	740
	7.5	840
	11.0	890

considerably, with values ranging from 740 to  $1.7 \times 10^9$  darcy. The radius of influence where a pressure of 1 inch of water could be measured was calculated by plotting the log of the pressure change at a specific monitoring point versus the distance from the vent well (Figure 6). The radius of influence at the Saddle Tank Farm Site is approximately 43 feet.

### **2.2.3 In Situ Respiration Test**


The results of the in situ respiration test for Saddle Tank Farm Site are presented in Appendix D. Each figure in Appendix D illustrates the oxygen, carbon dioxide, and helium concentrations as a function of time. An example of typical oxygen utilization at this site is shown in Figure 7, where oxygen utilization and carbon dioxide production at monitoring point G1-MPA-4.0' are illustrated. A summary of the oxygen utilization and carbon dioxide production rates and corresponding biodegradation rates is shown in Table 5. The biodegradation rates measured at this site were fairly high, with rates ranging from 11 to 30 mg/kg/day for oxygen utilization, and from 4.5 to 6.5 mg/kg/day for carbon dioxide production.

Loss of helium was insignificant at all monitoring points, indicating that the monitoring points were well sealed and that the oxygen depletion observed was a result of biodegradation.

Soil temperatures were measured during the in situ respiration test. Temperatures during the test ranged from 11.6°C to 12.9°C at monitoring point G1-MPA-4.0' and from 4.4°C to 5.6°C at monitoring point G1-MPA-11.0'.

### **2.2.4 Bioventing Demonstration**

The decision was made to install a bioventing system at Saddle Tank Farm Site. The bioventing system will not be installed at this site until spring 1993.



**Figure 6. Radius of Influence at the Saddle Tank Farm Site**






Figure 7. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G1-MPA-4.0' at the Saddle Tank Farm Site

**Table 5. Oxygen Utilization and Carbon Dioxide Production Rates During the In Situ Respiration Test at the Saddle Tank Farm Site**

<b>Sample Name</b>	<b>Oxygen Utilization Rate (%/hour)</b>	<b>Biodegradation Rate (mg/kg/day)</b>	<b>Carbon Dioxide Production Rate (%/hour)</b>	<b>Biodegradation Rate (mg/kg/day)</b>
Background	0.11	2.2	0.079	1.7
G1-MPA-4.0'	1.4	27	0.21	4.5
G1-MPA-7.5'	1.6	30	0.23	4.9
G1-MPB-7.5'	0.60	12	0.30	6.5
G1-MPC-11.0'	0.59	11	0.23	4.9

### **3.0 POWER PLANT SITE**

#### **3.1 Chronology of Events and Site Activities**

##### **3.1.1 Groundwater Measurements**

Groundwater was measured at one monitoring well at the Power Plant Site. Groundwater was recorded at the monitoring well at 12.23 feet.

##### **3.1.2 Soil Gas Survey**

On August 18, 1992, a limited soil gas survey was conducted to locate a suitable test area at Power Plant Site on August 18, 1992. Soil gases were sampled by driving a 5/8-inch-diameter stainless steel probe into the soil with a hammer drill. Soil gas was withdrawn with a vacuum pump and analyzed for oxygen, carbon dioxide, and TPH. Soil gas measurements were taken as described in Section 2.1.2.

The soil gas probes were driven to depths ranging from 2.5 to 7.5 feet at the several locations at the Power Plant Site. Once groundwater were encountered, the probes were not driven deeper. Table 6 provides the initial concentrations of oxygen, carbon dioxide, and TPH for the various locations at Power Plant Site. Relatively low concentrations of oxygen were found at most of the soil gas probes, with concentrations ranging from 0 to 14%. Relatively high concentrations of carbon dioxide (5.1 to 14.9%) and TPH (220 to 2,400 ppm) were encountered. The low concentrations of oxygen indicate that this area may respond to bioventing.

##### **3.1.3 Vent Well, Monitoring Point, and Thermocouple Installation**

On August 21, 1992, one vent well and four monitoring points were installed at the Power Plant Site, and soil samples were collected for analyses. The monitoring points were labeled G2-MPA, G2-MPB, G2-MPC, and G2-MPD. The locations of the vent well and monitoring points are shown in Figure 2. A cross section of the vent well and monitoring points showing site lithology and construction detail is shown in Figure 8. Figure 9 is a cross section that illustrates elevation changes.

**Table 6. Initial Soil Gas Composition at the Power Plant Site**

<b>Monitoring Point</b>	<b>Depth (ft)</b>	<b>Oxygen (%)</b>	<b>Carbon Dioxide (%)</b>	<b>TPH (ppm)</b>
GS-1	2.5	2.0	14.9	1,200
GS-4	2.5	0	11	2,400
	5.0	0	12	1,720
GS-5	2.5	8.8	8	440
	5.0	5.8	10	440
	7.5	1.2	12	1,480
GS-6	2.5	14	5.1	390
	5.0	10	8	220
	7.5	6.1	9.4	220




Figure 8. Cross Section of Vent Well and Monitoring Points at the Power Plant Site Showing Site Lithology and Construction Detail (not to scale)




Figure 9. Cross Section of Vent Well and Monitoring Points at the Power Plant Site Showing Elevation Differences

The vent well was installed at a depth of 8.0 feet into a 6-inch-diameter borehole. The vent well consisted of Schedule 40 2-inch-diameter PVC piping with 4.0 feet of ten-slot screen. The annular space corresponding to the screened area of the well was filled with silica sand, and the annular space above the screened interval was filled with bentonite to prevent short-circuiting of air to or from the surface.

Soil gas probes consisted of 1/4-inch tubing with a 1-inch-diameter, 6-inch screened area. The annular space corresponding to the screened area was filled with silica sand, whereas the interval between the screened areas was filled with bentonite, as was the annular space from the shallowest monitoring point to the ground surface. The monitoring points were installed at depths as follows:

- Monitoring point G2-MPA was installed at a depth of 10.0 feet into an 8-inch-diameter borehole. The monitoring point was screened to three depths: 4.0, 7.0, and 10.0 feet.
- Monitoring point G2-MPB was installed at a depth of 8.0 feet into an 8-inch-diameter borehole. The monitoring point was screened to three depths: 3.0, 5.5, and 8.0 feet.
- Monitoring point G2-MPC was installed at a depth of 8.0 feet into an 8-inch-diameter borehole. The monitoring point was screened to three depths: 3.0, 5.5, and 8.0 feet.
- Monitoring point G2-MPD was installed at a depth of 5.5 feet into an 8-inch-diameter borehole. The monitoring point was screened to two depths: 2.0 and 5.5 feet.

A Type J thermocouple was installed with monitoring points G2-MPA-4.0' and G2-MPA-10.0'.

#### **3.1.4 Soil and Soil Gas Sampling and Analyses**

Soil samples at the Power Plant Site were collected at depths of 4.0 to 4.5 feet, 5.5 to 5.0 feet, and 11.5 to 12.0 feet from the vent well borehole and were labeled GA2-V-4.0, GA2-V-5.5, and GA2-V-11.5, respectively. The samples were sent under chain of custody to Engineering-Science, Inc., Berkeley Laboratory for analyses of BTEX, TPH, alkalinity, moisture content, pH, iron, total phosphorous, and total Kjeldahl nitrogen.

Soil gas samples were collected from the vent well and from monitoring points G2-MPA and G2-MPC. These samples were labeled power plant vent well, power plant MPA red, and power plant MPC red, and were sent under chain of custody to Air Toxics, Ltd., in Rancho Cordova, California, for analysis of BTEX and TPH.

### **3.1.5 Soil Gas Permeability and Radius of Influence**

A detailed description of the method for conducting a soil gas permeability test, including equations to compute  $k$ , the soil gas permeability, is presented by the Test Plan and Technical Protocol (Hinchee et al., 1992).

Prior to air injection at the Power Plant Site, the monitoring points were allowed to set up for 96 hours. A portable 1-HP explosion-proof positive displacement blower unit was used to inject air. After air injection was initiated, pressure readings were taken approximately every 1 to 2 minutes for the first hour, then approximately every 10 minutes for the following hour. The Hyperventilate™ computer model was used to calculate the soil gas permeability.

### **3.1.6 In Situ Respiration Test**

Immediately following the soil gas permeability test at the Power Plant Site, air containing approximately 1% helium was injected into the soil for approximately 20 hours, beginning on August 26. Air was injected concurrently into the background monitoring well to measure the natural biodegradation of organic material in the soil. The setup for the in situ respiration test is described by the Test Plan and Technical Protocol (Hinchee et al., 1992). The pump used for air injection was a ½-HP diaphragm pump. Air and helium were injected through the following monitoring points at the depths indicated: G2-MPA-10.0'; G2-MPB-5.5'; G2-MPB-8.0'; and G2-MPC-8.0'. After the air/helium injection was turned off, the respiration gases were monitored periodically. The respiration test was terminated on August 29.



## 3.2 Results and Discussion

### 3.2.1 Soil and Soil Gas Analyses

Results of the soil analyses for BTEX and TPH at the Power Plant Site are presented in Table 7. The analytical report for this site is presented in Appendix B. All of the BTEX compounds were at concentrations below the detection limit in soil samples, whereas TPH concentrations ranged from 51 to 180 mg/kg. The soil gas analyses also showed relatively low BTEX and TPH concentrations with concentrations ranging from 1.1 ppmv (toluene) to 9.1 ppmv (total xylenes) and from 190 to 1,400 ppmv of TPH (Table 7). The results of the soil chemistry analyses are summarized in Table 8.

### 3.2.2 Soil Gas Permeability and Radius of Influence

The raw data for the soil gas permeability test at the Power Plant Site are presented in Appendix E. Using the Hyperventilate™ computer model, soil gas permeabilities were calculated at each of the monitoring points. These data are presented in Table 9. The soil gas permeability varied considerably, with values ranging from 840 to  $7.7 \times 10^8$  darcy. Typically, the radius of influence is calculated by plotting the log of the pressure change at a specific monitoring point versus the distance from the vent well. The radius of influence would then be the distance where 1 inch of water pressure can be measured. However, in this instance, 1 inch of water pressure was not achieved at any monitoring point (Figure 10); therefore, a radius of influence based on these specifications cannot be definitively determined at this site, other than to say it is less than 22 feet.

### 3.2.3 In Situ Respiration Test

The results of the in situ respiration test for the Power Plant Site are presented in Appendix F. Each figure in Appendix F illustrates the oxygen, carbon dioxide, and helium concentrations as a function of time. An example of typical oxygen utilization at this site is shown in Figure 11, where oxygen utilization and carbon dioxide production at monitoring point G2-MPB-8.0' are illustrated. A summary of the oxygen utilization and carbon dioxide production rates and the corresponding biodegradation rates is shown in Table 10. The biodegradation rates measured at this site were quite high, with rates ranging from 6.2 to 42 mg/kg/day for oxygen utilization, and from 1.9 to 8.0 mg/kg/day for carbon dioxide production.

**Table 7. Results From Soil and Soil Gas Analyses for BTEX and TPH at the Power Plant Site**

Matrix	Sample Name	Benzene (mg/kg)	Toluene (mg/kg)	Ethylbenzene (mg/kg)	Total Xylenes (mg/kg)	TPH <sup>1</sup> (mg/kg)
Soil	GA2-V-4.0	<0.0008	<0.0009	<0.0006	<0.0012	51
	GA2-V-5.5	<0.0008	<0.0006	<0.0012	<0.0009	61
	GA2-V-11.5	<0.0008	<0.0009	<0.0006	<0.0011	180
Matrix	Sample Name	Benzene (ppmv)	Toluene (ppmv)	Ethylbenzene (ppmv)	Total Xylenes (ppmv)	TPH <sup>2</sup> (ppmv)
Soil Gas	Power plant vent well	0.066	0.30	0.35	1.0	190
	Power plant MPA red	<0.11	1.1	1.8	7.4	1,100
	Power plant MPC red	<0.11	2.0	2.0	9.1	1,400

<sup>1</sup> Referenced to a reference oil composed of a mixture of 2,2,4-trimethylpentane, *n*-hexadecane, and chlorobenzene.

<sup>2</sup> TPH referenced to gasoline (molecular weight = 100).

**Table 8. Results From Soil Chemistry Analyses at the Power Plant Site**

Parameter	Sample Name		
	GA2-V-4.0	GA2-V-5.5	GA2-V-11.5
Alkalinity (mg/kg CaCO <sub>3</sub> )	480	500	500
Moisture (% by weight)	23.5	22.6	20.8
pH	7.7	7.8	7.8
Iron (mg/kg)	27,700	19,900	24,900
Total Phosphorous (mg/kg)	750	650	720
Total Kjeldahl Nitrogen (mg/kg)	700	670	490

**Table 9. Results of Hyperventilate™ Soil Gas Permeability Analysis at the Power Plant Site**

Monitoring Point	Depth (ft)	Soil Gas Permeability (darcy)
G2-MPA	4.0	10
	7.0	$3.2 \times 10^7$
	10.0	$1.9 \times 10^6$
G2-MPB	3.0	7,000
	5.5	4,000
	8.0	320,000
G2-MPC	3.0	$7.7 \times 10^8$
	5.5	$> 1.0 \times 10^{10}$
	8.0	$1.2 \times 10^9$
G2-MPD	2.0	1,400
	5.5	840




Figure 10. Radius of Influence at the Power Plant Site




Figure 11. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G2-MPB-8.0' at the Power Plant Site

**Table 10. Oxygen Utilization and Carbon Dioxide Production Rates During the In Situ Respiration Test at the Power Plant Site**

Sample Name	Oxygen Utilization Rate (%/hour)	Biodegradation Rate (mg/kg/day)	Carbon Dioxide Production Rate (%/hour)	Biodegradation Rate (mg/kg/day)
Background	0.11	2.2	0.079	1.7
G2-MPA-10.0'	0.32 7.68	6.2 6.13	0.087	1.9
G2-MPB-5.5'	0.95 22.8	18 18.21	0.18	3.9
G2-MPB-8.0'	2.2 52.8	42 42.17	0.37	8.0
G2-MPC-8.0'	2.2 52.8	42 42.17	0.33	7.1

Loss of helium was insignificant at all monitoring points, indicating that the monitoring points were well sealed and that the oxygen depletion observed was a result of biodegradation.

Soil temperatures were measured during the in situ respiration test. Temperatures during the test ranged from 13.1°C to 14.0°C at monitoring point G2-MPA-4.0' and from 10.7°C to 11.3°C at monitoring point G2-MPA-10.0'.

#### **3.2.4 Bioventing Demonstration**

The decision was made to install a bioventing system at the Power Plant Site. The bioventing system will not be installed until spring 1993.

## **4.0 MILLION GALLON HILL SITE**

### **4.1 Chronology of Events and Site Activities**

Existing wells were used at the Million Gallon Hill Site to screen for free product and soil gas concentrations. Due to the depth to groundwater, conventional soil gas survey methods were not employed. An existing well was used as a vent well for the air permeability test. No soil samples were taken at this location.

#### **4.1.1 Groundwater Measurements**

Groundwater and free product measurements were taken in an existing well which was used as the vent well at the Million Gallon Hill Site. The depth to free product was recorded at 31.87 feet, the depth to water was 31.91 feet, and the depth to the bottom of the well was 43 feet.

#### **4.1.2 Soil Gas Survey**

On August 19, 1992, a soil gas survey was conducted with existing vent wells to measure soil gas concentrations at the Million Gallon Hill Site. Measurements of soil gas were taken as described in Section 2.1.2.

Oxygen concentrations were measured in the vent well and in several soil gas probes. Oxygen concentrations ranged from 0 to 17%, and TPH concentrations ranged from 60 to 71,200 ppm (Table 11). These measurements indicated that this area may be suitable for bioventing.

#### **4.1.3 Vent Well, Monitoring Point, and Thermocouple Installation**

On August 27, three monitoring points were installed. The monitoring points were labeled G3-MPA, G3-MPB, and G3-MPC. The locations of the vent well and monitoring points are shown in Figure 3. A cross section of a generic vent well and the monitoring points showing site lithology and construction detail is shown in Figure 12.

**Table 11. Initial Soil Gas Composition at the Million Gallon Hill Site**

<b>Monitoring Point</b>	<b>Depth (ft)</b>	<b>Oxygen (%)</b>	<b>Carbon Dioxide (%)</b>	<b>TPH (ppm)</b>
GS-1	10.0	17.0	2.9	60
	20.0	14.2	3.9	60
	27.5	0	5.5	600
GS-3	27.5	0	6.5	1,000
GS-4	20.0	16.0	2.5	4,400
Vent Well		8.1	8.5	71,200






Figure 12. Cross Section of Vent Well and Monitoring Points at the Million Gallon Hill Site Showing Site Lithology and Construction Detail (not to scale)

Soil gas probes were sacrificial points which consisted of ¼-inch tubing with an aluminum, 4-inch screened area. No soil borings were created nor was any sand added. A small amount of wetted bentonite was added at the surface. The sacrificial points were driven into the soil using a hammer drill. The monitoring points were installed at depths as follows:

- Monitoring point G3-MPA was installed at a depth of 27.5 feet. The monitoring point was screened to three depths: 10.0, 20.0, and 27.5 feet.
- Monitoring point G3-MPB was installed at a depth of 27.5 feet. The monitoring point was screened to three depths: 10.0, 20.0, and 27.5 feet.
- Monitoring point G3-MPC was installed at a depth of 20 feet. The monitoring point was screened to two depths: 10.0 and 20.0 feet.

A Type J thermocouple was installed with monitoring points G3-MPA-10.0' and G3-MPA-27.5'.

#### **4.1.4 Soil Gas Sampling and Analyses**

Soil gas samples were collected at the Million Gallon Hill Site from the vent well and from monitoring points G3-MPA and G3-MPB, and were labeled M vent well (Radian), M-MPA 27.5, and M-MPB 27.5. These samples were sent under chain of custody to Air Toxics, Ltd., in Rancho Cordova, California, for analyses of BTEX and TPH.

#### **4.1.5 Soil Gas Permeability and Radius of Influence**

A detailed description of the method for conducting a soil gas permeability test, including equations to compute  $k$ , the soil gas permeability, is presented by the Test Plan and Technical Protocol (Hinchee et al., 1992).

The monitoring points at the Million Gallon Hill Site were allowed to set up for 96 hours prior to air injection. A portable 1-HP explosion-proof positive displacement blower unit was used to inject air. After air injection was initiated, pressure readings were taken approximately every 1 to 2 minutes for the first hour, then approximately every 10 minutes for the following hour. The Hyperventilate™ computer model was used to calculate the soil gas permeability.

#### **4.1.6 In Situ Respiration Test**

Immediately following the soil gas permeability test at the Million Gallon Hill Site, air containing approximately 1% helium was injected into the soil for approximately 20 hours, beginning on September 1. Air was injected concurrently into the background monitoring well to measure the natural biodegradation of organic material in the soil. The setup for the in situ respiration test was as described by the Test Plan and Technical Protocol (Hinchee et al., 1992). The pump used for air injection was a ½-HP diaphragm pump. Air and helium were injected through the following monitoring points: G3-MPA-20.0'; G3-MPA-27.5'; G3-MPB-20.0'; and G3-MPB-27.5'. The respiration gases were monitored periodically after the air/helium injection was turned off. The respiration test was terminated on September 4.

### **4.2 Results and Discussion**

#### **4.2.1 Soil Gas Analyses**

Results of the soil gas analyses for BTEX and TPH at the Million Gallon Hill Site are presented in Table 12. The analytical report for this site is presented in Appendix B. The soil gas analyses showed relatively low BTEX and TPH concentrations, with concentrations ranging from 0.082 ppmv (benzene) to 13 ppmv (benzene) and from 26 to 3,600 ppmv of TPH.

#### **4.2.2 Soil Gas Permeability and Radius of Influence**

The raw data for the soil gas permeability test at Million Gallon Hill Site are presented in Appendix G. Using the Hyperventilate™ computer model, soil gas permeabilities were calculated at each of the monitoring points. These data are presented in Table 13. The soil gas permeability was somewhat variable, with values ranging from less than  $1.0 \times 10^{-5}$  up to 590 darcy. The radius of influence where 1 inch of water could be measured was calculated by plotting the log of the pressure change at a specific monitoring point versus the distance from the vent well (Figure 13). The radius of influence at the Million Gallon Hill Site is approximately 33 feet.

Table 12. Results From Soil Gas Analyses for BTEX and TPH at the Million Gallon Hill Site

Matrix	Sample Name	Benzene (ppmv)	Toluene (ppmv)	Ethylbenzene (ppmv)	Total Xylenes (ppmv)	TPH <sup>1</sup> (ppmv)
Soil Gas	M vent well (Radian)	0.082	0.30	0.16	0.035	26
	M-MPA 27.5	6.0	5.8	3.8	0.94	3,600
	M-MPB 27.5	13	11	3.6	0.94	2,300

<sup>1</sup> TPH referenced to gasoline (molecular weight = 100).

Table 13. Results of Hyperventilate™ Soil Gas Permeability Analysis at the Million Gallon Hill Site

Monitoring Point	Depth (ft)	Soil Gas Permeability (darcy)
G3-MPA	10.0	590
	20.0	6.1
	27.5	240
G3-MPB	10.0	20
	20.0	27
	27.5	28
G3-MPC	10.0	$< 1.0 \times 10^{-5}$
	20.0	$< 1.0 \times 10^{-5}$




Figure 13. Radius of Influence at the Million Gallon Hill Site

### 4.2.3 In Situ Respiration Test

The results of the in situ respiration test for the Million Gallon Hill Site are presented in Appendix H. Each figure in Appendix H illustrates the oxygen and helium concentrations as a function of time. An example of typical oxygen utilization at this site is shown in Figure 14, where oxygen and helium at monitoring point G3-MPA-27.5' are illustrated. A summary of the oxygen utilization rates and corresponding biodegradation rates is shown in Table 14. The biodegradation rates measured at this site were fairly consistent between the monitoring points, with rates ranging from 4.5 to 11 mg/kg/day for oxygen utilization, and 1.0 to 2.6 mg/kg/day for carbon dioxide production.

Loss of helium was insignificant at all monitoring points, indicating that the monitoring points were well sealed and that the oxygen depletion observed was a result of biodegradation.

Soil temperatures were not monitored at this site during the in situ respiration test.

### 4.2.4 Bioventing Demonstration

The decision was made to install a bioventing system at Million Gallon Hill Site. The bioventing system will not be installed until spring 1993.

**Table 14. Oxygen Utilization and Carbon Dioxide Production Rates During the In Situ Respiration Test at the Million Gallon Hill Site**

Sample Name	Oxygen Utilization Rate (%/hour)	Biodegradation Rate (mg/kg/day)	Carbon Dioxide Production (%/hour)	Biodegradation Rate (mg/kg/day)
Background	0.11	2.2	0.079	1.7
G3-MPA-20.0'	0.24 5.76	4.5 4.60	0.12	2.6
G3-MPA-27.5'	0.51 12.24	9.7 9.79	0.048	1.0
G3-MPB-20.0'	0.42 10.08	8.0 8.05	0.091	2.0
G3-MPB-27.5'	0.57 13.68	11 10.92	0.094	2.0




Figure 14. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G3-MPA-27.5' at the Million Gallon Hill Site

## **5.0 CAMPION POL TANK SITE**

### **5.1 Chronology of Events and Site Activities**

#### **5.1.1 Groundwater Measurements**

Groundwater levels were measured at 7.9 feet in the vent well described in Section 5.1.3.

#### **5.1.2 Soil Gas Survey**

A limited soil gas survey was conducted on August 18, 1992 to locate a suitable test area at the Campion POL Tank Site. Soil gases were sampled by driving a 5/8-inch diameter stainless steel probe into the soil with a hammer drill. Soil gas was withdrawn with a vacuum pump and analyzed for oxygen, carbon dioxide, and TPH. Soil gas measurements were taken as described in Section 2.1.2.

The soil gas probes were driven to depths ranging from 2.5 to 7.5 feet at several locations at the Campion POL Tank Site. Once groundwater were encountered, the probes were not driven deeper. Table 15 provides the initial concentrations of oxygen, carbon dioxide, and TPH for the various locations at the Campion POL Tank Site. Relatively low oxygen concentrations were found at most of the soil gas probes, whereas relatively high concentrations of carbon dioxide and TPH were encountered. These concentrations indicate that this area may respond to bioventing.

#### **5.1.3 Vent Well, Monitoring Point, and Thermocouple Installation**

On August 19 the vent well and three monitoring points were installed at the Campion POL Tank Site, and soil samples were collected for analyses. The monitoring points were labeled C1-MPA, C1-MPB, and C1-MPC. The locations of the vent well and monitoring points are shown in Figure 4. A cross section of the vent well and monitoring points showing site lithology and construction detail is shown in Figure 15.

The vent well was installed at a depth of 9.0 feet into a 6-inch-diameter borehole. The vent well consisted of Schedule 40 2-inch-diameter PVC piping with 4.5 feet of ten-slot screen. The annular space corresponding to the screened area of the well was filled with silica sand, whereas the



Table 15. Initial Soil Gas Composition at the Campion POL Tank Site

Monitoring Point	Depth (ft)	Oxygen (%)	Carbon Dioxide (%)	TPH (ppm)
GS-1	2.5	20.9	0.05	20
	5.0	15.0	4.8	2,000
GS-2	2.5	0.5	10.0	7,800
GS-3	2.5	1.0	9.9	1,040
GS-4	2.5	0	11.0	1,280
	5.0	0.1	11.0	1,680
	7.5	6.0	9.0	760
GS-5	2.5	2.0	9.0	2,400
	5.0	2.0	9.1	3,200
GS-6	2.5	3.8	6.5	640
GS-7	5.0	1.0	10.0	2,800




Figure 15. Cross Section of Vent Well and Monitoring Points at the Campion POL Tank Site Showing Site Lithology and Construction Detail (not to scale)

annular space above the screened interval was filled with bentonite to prevent short-circuiting of air to or from the surface.

Soil gas probes consisted of 1/4-inch tubing connected to a 1-inch-diameter, 6-inch screened area. The annular space corresponding to the screened area was filled with silica sand, whereas the interval between the screened areas was filled with bentonite, as was the annular space from the shallowest monitoring point to the ground surface. The monitoring points were installed at a depth of 7.3 feet into an 8-inch-diameter borehole and screened to three depths: 3.0, 5.0, and 7.0 feet.

A Type J thermocouple was installed with monitoring points C1-MPA-3.0' and C1-MPA-7.0'.

#### **5.1.4 Soil and Soil Gas Sampling and Analyses**

Soil samples were collected at depths of 4.0 to 4.5 feet, 6.0 to 6.5 feet, and 9.0 to 9.5 feet from the vent well borehole and were labeled CA-V-4.0, CA-V-6.0, and CA-V-9.0, respectively. The samples were sent under chain of custody to Engineering-Science, Inc., Berkeley Laboratory for analysis of BTEX, TPH, alkalinity, moisture content, pH, iron, total phosphorous, and total Kjeldahl nitrogen.

Soil gas samples were collected from the vent well and monitoring points C1-MPA and C1-MPC and were labeled vent well, MPA red, and monitor point C blue. These samples were sent under chain of custody to Air Toxics, Ltd., in Rancho Cordova, California, for analyses of BTEX and TPH.

#### **5.1.5 Soil Gas Permeability and Radius of Influence**

A detailed description of the method for conducting a soil gas permeability test, including equations to compute  $k$ , the soil gas permeability, is presented by the Test Plan and Technical Protocol (Hinchee et al., 1992).

The monitoring points were left in place for 96 hours prior to air injection. Air was injected with a portable 1-HP explosion-proof positive displacement blower unit. After air injection was initiated, pressure readings were taken approximately every 1 to 2 minutes for the first hour, then approximately every 10 minutes for the following hour. The Hyperventilate™ computer model was used to calculate the soil gas permeability.

### 5.1.6 In Situ Respiration Test

Immediately following the soil gas permeability test, air containing approximately 1% helium was injected into the soil for approximately 20 hours beginning on August 28. Air was injected concurrently into the background monitoring well to measure the natural biodegradation of organic material in the soil. The in situ respiration test was set up as described in the Test Plan and Technical Protocol (Hinchee et al., 1992). The pump used for air injection was a ½-HP diaphragm pump. Air and helium were injected through monitoring points C1-MPA-7.0', C1-MPB-5.0', C1-MPB-7.0', and C1-MPC-5.0'. The respiration gases were monitored periodically after the air/helium injection was turned off. The respiration test was terminated on August 31.

## 5.2 Results and Discussion

### 5.2.1 Soil and Soil Gas Analyses

Results of the soil analyses for BTEX and TPH are presented in Table 16. The analytical report for this data is presented in Appendix B. Relatively low concentrations of BTEX and TPH were found in soil samples, with concentrations ranging from below detection limits (all BTEX compounds) up to 0.74 mg/kg (toluene) and from 180 to 1,700 mg/kg of TPH. The soil gas analyses also showed relatively low BTEX and TPH concentrations, with concentrations ranging from less than 0.002 ppmv (benzene) up to 0.39 ppmv (total xylenes) and from 10 to 750 ppmv of TPH (Table 16). The results from the soil chemistry analyses are summarized in Table 17.

### 5.2.2 Soil Gas Permeability and Radius of Influence

The raw data for the soil gas permeability test at the Campion POL Tank Site are presented in Appendix I. Using the Hyperventilate™ computer model, soil gas permeabilities were calculated at each of the monitoring points. These data are presented in Table 18. The soil gas permeability varied considerably, with values ranging from less than  $1.0 \times 10^{-5}$  up to greater than  $1.0 \times 10^{10}$  darcy. The radius of influence where 1 inch of water could be measured was calculated by plotting the log of the pressure change at a specific monitoring point versus the distance from the vent well (Figure 16). The radius of influence at the Campion POL Tank Site is approximately 5 feet.

**Table 16. Results From Soil and Soil Gas Analyses for BTEX and TPH at the Campion POL Tank Site**

<b>Matrix</b>	<b>Sample Name</b>	<b>Benzene (mg/kg)</b>	<b>Toluene (mg/kg)</b>	<b>Ethylbenzene (mg/kg)</b>	<b>Total Xylenes (mg/kg)</b>	<b>TPH<sup>1</sup> (mg/kg)</b>
Soil	CA-V-4.0	<0.0034	<0.0039	<0.0028	<0.09	180
	CA-V-6.0	<0.0032	0.74	<0.0026	0.47	1,700
	CA-V-9.0	0.085	<0.0017	<0.0012	0.092	390
<b>Matrix</b>	<b>Sample Name</b>	<b>Benzene (ppmv)</b>	<b>Toluene (ppmv)</b>	<b>Ethylbenzene (ppmv)</b>	<b>Total Xylenes (ppmv)</b>	<b>TPH<sup>2</sup> (ppmv)</b>
Soil Gas	Vent well	0.05	0.069	0.15	0.39	750
	MPA red	0.014	0.033	0.006	0.22	1.4
	Monitor point C blue	<0.002	0.019	0.005	0.052	10

<sup>1</sup> Referenced to a reference oil composed of a mixture of 2,2,4-trimethylpentane, *n*-hexadecane, and chlorobenzene.

<sup>2</sup> TPH referenced to gasoline (molecular weight = 100).

Table 17. Results From Soil Chemistry Analyses at the Campion POL Tank Site

Parameter	Sample Name		
	CA-V-4.0	CA-V-6.0	CA-V-9.0
Alkalinity (mg/kg $\text{CaCO}_3$ )	230	190	490
Moisture (% by weight)	11.2	5.9	19.7
pH	8.3	8.3	7.6
Iron (mg/kg)	15,800	11,000	18,700
Total Phosphorus (mg/kg)	510	510	690
Total Kjeldahl Nitrogen (mg/kg)	510	430	1,200

Table 18. Results of Hyperventilate™ Soil Gas Permeability Analysis at the Campion POL Tank Site

Monitoring Point	Depth (ft)	Soil Gas Permeability (darcy)
C1-MPA	3.0	$< 1.0 \times 10^{-5}$
	5.0	$< 1.0 \times 10^{-5}$
	7.0	$< 1.0 \times 10^{-5}$
C1-MPB	3.0	$< 1.0 \times 10^{-5}$
	5.0	$< 1.0 \times 10^{-5}$
	7.0	1.2
C1-MPC	3.0	$2.1 \times 10^9$
	5.0	$> 1.0 \times 10^{10}$
	7.0	$> 1.0 \times 10^{10}$




Figure 16. Radius of Influence at the Campion POL Tank Site

### 5.2.3 In Situ Respiration Test

The results of the in situ respiration test for the Campion POL Tank Site are presented in Appendix J. Each figure in Appendix J illustrates the oxygen, carbon dioxide, and helium concentrations as a function of time. An example of typical oxygen utilization at this site is shown in Figure 17, which illustrates oxygen utilization and carbon dioxide production at monitoring point C1-MPC-5.0'. The oxygen utilization and carbon dioxide production rates and corresponding biodegradation rates are summarized in Table 19. The biodegradation rates measured at this site were quite high, with rates ranging from 6.4 to 29.0 mg/kg/day for oxygen utilization, and from 2.6 to 6.0 mg/kg/day for carbon dioxide production.

Loss of helium was insignificant at all monitoring points, indicating that the monitoring points were well sealed and that the oxygen depletion observed was a result of biodegradation.

Soil temperatures were measured during the in situ respiration test. Temperatures during the test ranged from 9.3°C to 9.8°C at monitoring point C1-MPA-3.0' and from 4.2°C to 5.4°C at monitoring point C1-MPA-7.0'.

### 5.2.4 Bioventing Demonstration

Although high biodegradation rates indicated that this site would be a good candidate for bioventing, a system could not be installed due to the unavailability of a power source.

**Table 19. Oxygen Utilization and Carbon Dioxide Production Rates During the In Situ Respiration Test at the Campion POL Tank Site**

Sample Name	Oxygen Utilization Rate (%/hour)	Biodegradation Rate (mg/kg/day)	Carbon Dioxide Production Rate (%/hour)	Biodegradation Rate (mg/kg/day)
Background	0.11	2.2	0.079	1.7
C1-MPA-7.0'	1.5	29	0.28	6.0
C1-MPB-5.0'	0.74	14	0.14	3.1
C1-MPB-7.0'	1.4	27	0.15	3.2
C1-MPC-5.0'	0.33	6.4	0.12	2.6






Figure 17. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point C1-MPC-5.0' at the Campion POL Tank Site

## 6.0 BACKGROUND AREA

The background vent well and monitoring points were located upgradient from the contaminated site at Campion AFS, approximately 200 feet away. The vent well was installed at a depth of 8.5 feet. The vent well consisted of Schedule 40 2-inch-diameter PVC piping with 5.0 feet of ten-slot screen. The annular space corresponding to the screened area of the well was filled with silica sand, whereas the annular space above the screened interval was filled with bentonite to prevent short-circuiting of air to or from the surface. The site lithology at this area was representative of that in the contaminated areas.

An in situ respiration test was conducted at the background area beginning on August 28, 1992 after 24 hours of air injection. The test was concluded on August 31. The biodegradation rate was relatively high at this area, considering that it is a background, uncontaminated location (Figure 18).

## 7.0 FUTURE WORK

The bioventing systems at Galena AFS will be installed in spring 1993. Once the system is operating, base personnel will be required to perform a simple weekly system check to ensure that the blower is operating within its intended flowrate, pressure, and temperature range. An on-site briefing for base personnel who will be responsible for blower system checks will be conducted when the blowers are installed. The principle of operation will be explained, and a simple checklist and logbook will be provided for blower data. Base personnel will be asked to perform minor maintenance activities, such as replacing filters or gauges, or draining condensate from knockout chambers, but they will not be expected to perform complicated repairs or analyze gas samples. Replacement filters and gauges will be provided and shipped to the base, and serious problems, such as motor or blower failures, will be corrected by Battelle.

The progress of this system will be monitored by conducting semiannual respiration tests in the vent well and in each monitoring point and by regularly measuring the oxygen, carbon dioxide, and hydrocarbon concentrations in the extracted soil gas and comparing them to background levels. At least twice each year, the progress of the bioventing test will be reported to the base POC.




Figure 18. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at the Background Area

## 8.0 REFERENCE

Hinchee, R.E., S.K. Ong, R.N. Miller, D.C. Downey, and R. Frandt. 1992. *Test Plan and Technical Protocol for a Field Treatability Test for Bioventing* (Rev. 2), Report prepared by Battelle Columbus Operations, U.S. Air Force Center for Environmental Excellence, and Engineering Sciences, Inc. for the U.S. Air Force Center for Environmental Excellence, Brooks Air Force Base, Texas.

**APPENDIX A**  
**TEST PLAN FOR GALENA AND CAMPION AFS, ALASKA**



**Battelle**

*Putting Technology To Work*

505 King Avenue  
Columbus, Ohio 43201-2693  
Telephone (614) 424-6424  
Facsimile (614) 424-5263

August 5, 1992

Capt. Catherine Vogel  
HQ AFCESA/RAVW  
139 Barnes Drive  
Tyndall Air Force Base,  
Florida 32403-5319

Dear Cathy:

**SUBJECT: TEST PLAN FOR BIOVENTING INITIATIVE  
FIELD TEST AT GALENA AFS AND CAMPION AFS, AK**

This letter was prepared to accompany the report "Test Plan and Technical Protocol for a Field Treatability Test for Bioventing." The protocol document was developed as a generic test plan for the Air Force Bioventing Initiative Project in which Galena AFS is participating. This letter outlines site specific information to support the generic test plan.

The sites anticipated for the bioventing test initiative are Tanks 37 and 38, Tank 49 (base power plant), and the Saddle Tank farm area at Galena AFS, and POL leak site 1 (former location of the Campion fuel tank farm) at Campion AFS. The selection of these sites was based on observations I made during my site visit to Galena/Campion AFS and with the concurrence of base POC 1<sup>st</sup> Lieutenant Kevin Swisher.

The purpose of this project is to investigate the feasibility of using the bioventing technology to remediate petroleum contaminated soils at the above mentioned facilities.

Site Descriptions-

Galena AFS is located approximately 280 miles west of Fairbanks, AK on the Yukon river. The installation is a forward operating base of the U.S. Air Force Alaska Air Command. Approximately 350 military personnel are currently assigned to the base and the population of the adjacent community of Galena is approximately 750. Galena is not connected by road to any other community and is only accessible by air or water.

Campion AFS, located approximately 12 miles east of Galena, was deactivated and demolished in the early to mid- 1980's. The site is accessible by gravel road from Galena AFS. There are no buildings and electrical power is currently not accessible from the site.

**Tanks 37 and 38 (Galena)-** Tank 37 and tank 38 are large capacity above ground petroleum storage tanks containing diesel and JP-4, respectively (see figure 1). The tanks are located in a fuel storage tank farm along with JP-4 storage tanks 41 and 42. The tank farm is located on a fill mound built up approximately 30 ft above grade. Groundwater is located at approximately 40 ft below the tanks and soil analytical data indicates that contamination is primarily encountered at depths greater than 20 ft. Table 1 summarizes the available analytical data for Tanks 37 and 38.

**Saddle Tank Farm (Galena)-** The saddle tank farm area is located east of Tanks 37 and 38. The tank farm contains approximately 20 above ground petroleum storage tanks in a diked area. Groundwater at the site is typically encountered at less than 10 ft. The base POC located an area just east of the containment dike that is believed to be a good candidate site for the bioventing demonstration. This site is located several hundred feet from a vapor extraction pilot study being conducted by Radian Corporation. Soil analytical data has not been made available for this site.

**Diesel Tank 49 (Galena)-** Tank 49 is a 20,000 gallon diesel tank located adjacent to the base power plant (see figure 1). Groundwater is encountered at approximately 10 ft at the site. Soil analytical data has indicated TPH concentrations in excess of 10,000 ppm (see Table 2).

**POL Leak Site 1 (Campion)-** POL Leak Site 1 is located in the former petroleum storage tank farm at Campion AFS. The tanks have been removed, but their former location is evidenced by circular gravel pads inside a diked area. Soil samples from the site have indicated TPH concentrations of 300 to 500 ppm. Groundwater at the site is present at approximately 10 ft.

#### Project activities-

The following field activities are planned for the bioventing project at Galena/Campion AFS. The same procedures will be followed at each site (except Tanks 37 and 38). Additional detail can be found in Section 5.0 of the generic test plan and technical protocol.

- 1- A small scale soil gas survey will be conducted to identify an appropriate location for installation of the bioventing system. Soil vapor from the candidate site must exhibit high petroleum hydrocarbon concentrations (10,000 ppm or greater), relatively low O<sub>2</sub> concentrations (0 % to 2.0 %), and relatively high CO<sub>2</sub> concentrations (depending on soil type, 2.0 % to 10.0 %). An uncontaminated background location will also be identified.
- 2- Once the installation sites are located one vent well and three 3-level soil gas monitoring points will be installed in the contaminated location and one vent well will be installed in the background area. The wells and monitoring points will be installed using a two-man power auger to bore down to just above the water table.




FIGURE 1. SITE MAP FOR TANKS 37 & 38, AND TANK 41, GALENA AFS, ALASKA.



TABLE 1. CONTAMINANT CONCENTRATIONS AT TANKS 37 AND 38, GALENA AFS, AK.

CONCENTRATION  
(mg/Kg)

SAMPLE LOCATION	DEPTH(ft)	TPH	BENZENE	TOLUENE	ETHYLBENZENE	XYLENE
MW-2	20	6460	0.336	1.4	1.4	4.23
MW-3	10	<11.5	<.021	<.02	<.02	<.063
MW-4	14.5	28.3	<.018	<.02	<.02	<.055
MW-5	20.5	<11.2	<.02	<.02	<.02	<.059
MW-5	29.5	327	14.3	71	32	126
B-1	19	40.6	0.024	0.05	<.02	<.06
B-1	29	169	0.293	3.6	1.5	6.94
B-1	39	7720	3.19	40	13	93.7
B-1	44	7650	4.55	49	17	85.3
B-2	14	26.8	<.02	<.02	<.02	<.061
B-2	24	322	0.027	<.01	0.08	0.3
B-2	34	3060	0.488	3	3.9	15.6
B-2	44	18200	1.93	11	9.5	34.2
B-3	5	1140	<.042	<.04	<.04	<.127
B-3	19	17.9	0.14	1.8	3.2	19.8
B-3	29	5810	0.061	1.6	2.3	12.6
B-3	39	1670	0.526	8.1	14	87.6

TABLE 2. CONTAMINANT CONCENTRATIONS AT TANK 49, GALENA AFS, AK.

CONCENTRATION  
(mg/Kg)

SAMPLE LOCATION	DEPTH(ft)	TPH	BENZENE	TOLUENE	ETHYLBENZENE	XYLENE
B-1	5	7630	<.019	0.16	<.02	5.72
B-1	10	12500	<.184	4.7	23	110
B-2	1	2360	0.74	12	37	356
B-2	9	6380	<.061	0.47	<.06	20.5
MW-2	1	13100	0.239	5.9	9.9	66.7
MW-2	9.5	1270	<.019	0.08	<.02	3.51

Three to four soil samples will be collected for chemical/physical analysis.

- 3- The air permeability test will be conducted in the contaminated test location.
- 4- Following the air permeability test, in situ respiration tests will be conducted in both the contaminated and the background test locations.
- 5- Depending on the results of the air permeability test and the in situ respiration test, a decision will be made whether or not to install a blower system in the contaminated area for the long term bioventing test. If the decision is made to install, the blower will be plumbed to the vent well and bioventing will be started (assuming power is available). Site personnel will be trained for blower operation prior to Battelle leaving the site.

#### Procedures for Tanks 37 and 38-

The same basic procedures will be followed at the Tanks 37 and 38 site, with the following exceptions:

- 1- Existing site wells will be screened for free product and soil vapor concentrations. Due to the depth to groundwater, conventional soil gas survey methods will not be employed.
- 2- A existing well will be selected for use as a vent well.
- 3- Sacrificial soil vapor probes will be driven to the maximum depth possible with a 20 lb impact drill. These points, along with other existing wells, will be used for soil gas and pressure monitoring points.

#### Schedule-

Field activities at Galena/Campion are planned to begin on August 17, 1992. Battelle will have 2 to 3 people on site for approximately 3 weeks.

#### Base Support-

Galena AFS needs to be able to provide the following:

- Digging permits and utility clearance for all sites need to be obtained prior to the

initiation of the field work. Underground utilities should be clearly marked to reduce the chance of utility damage or personal injury during soil gas probe and well installation. Battelle will not be able to begin field operations without these clearances.

- Electrical power will need to be easily accessible from the project site. The air permeability test and in situ respiration test can be performed using a gasoline powered electric generator. The operation of the bioventing system will require a permanent 220/110 V power source. If power will not be available immediately after the test is completed the bioventing system will be installed for start-up at a later date. Due to the remote location of the Campion sites no blower will be installed during the initial field effort. If the Air Force determines that installation is desirable at a later date (after power requirements for the blower can be met) Battelle will install the blower during a scheduled Galena AFS site visit.
- Regulatory approval, if any is required, will need to be obtained by the base prior to start-up of the bioventing system. The system will likely be configured for air injection so there will be no point source vapor emission from the system. The wells to be installed will not intersect the apparent water table and no groundwater will be pumped. Ms. Laura Noland of the Alaska Department of Environmental Conservation has indicated that there will be no problem installing and operating the bioventing system (configured for injection), pending her review of this site specific test plan.
- Drums for containment of contaminated soil cuttings. The base will be responsible for disposal of any contaminated soils.
- Base and site clearance will be required for Battelle's site employees. We will furnish the base POC with personal information for each person at least one week prior to starting field operations.

Capt. Catherine Vogel  
Tyndall Air Force Base

8

August 5, 1992

Thank you for your support for this bioremediation research project. If you have any questions please feel free to call me at (614) 424-6122.

Sincerely,

Jeffrey A. Kittel  
Researcher  
Environmental Technology Department

JAK:sh  
Enclosure

**APPENDIX B**  
**ANALYTICAL REPORT FOR THE SADDLE TANK FARM SITE,**  
**THE POWER PLANT SITE, THE MILLION GALLON HILL SITE,**  
**AND THE CAMPION POL TANK SITE**

**@ AIR TOXICS LTD.**

AN ENVIRONMENTAL ANALYTICAL LABORATORY

**WORK ORDER #: 9209042****Work Order Summary**

**CLIENT:** Mr. Jeff Kittle  
Battelle  
505 King Ave.  
Columbus, OH 43201

**BILL TO:** Accounts Payable  
Engineering Science  
1700 Broadway Ste. 900  
Denver, CO 80290

**PHONE:** 614-424-6122

**FAX:** 614-424-3667

**DATE RECEIVED:** 9/9/92

**DATE REPORTED:** 9/17/92

**INVOICE #** 8461

**P.O. #** DE 268.03

**AMOUNT:** \$1,655.97

**PROJECT #**

<u>FRACTION #</u>	<u>NAME</u>	<u>TEST</u>	<u>Receipt</u>	
			<u>VAC./Press.</u>	<u>PRICE</u>
01A	Vent Well	TO-3	1.5 "Hg	\$120.00
02A	Power Plant MPC Red	TO-3	1.5 "Hg	\$120.00
03A	MPC Red	TO-3	3.5 "Hg	\$120.00
04A	M-MPB 27.5	TO-3	15.5 "Hg	\$120.00
05A	M-MPA 27.5	TO-3	1.5 "Hg	\$120.00
06A	M Vent Well (Radian)	TO-3	2.0 "Hg	\$120.00
07A	Vent Well	TO-3	2.0 "Hg	\$120.00
08A	Power Plant Vent Well	TO-3	1.5 "Hg	\$120.00
09A	Monitor Point C blue	TO-3	0.5 "Hg	\$120.00
10A	Power Plant MPA Red	TO-3	3.5 "Hg	\$120.00
11A	MPA Red, Little or No Vacuum Flow	TO-3	0.2 psi	\$120.00
12A	MPA Red	TO-3	1.0 "Hg	\$120.00
12B	MPA Red Duplicate	TO-3	1.0 "Hg	NC
13A	Method Spike	TO-3	NA	NC
14A	Lab Blank	TO-3	NA	NC
14B	Lab Blank	TO-3	NA	NC

Misc. Charges 1 Liter SUMMA Canister Preparation (12) @ \$10.00 each. \$120.00  
Shipping (8/21/92) \$95.97

REVIEWED BY: 

DATE: 9/18/92

CERTIFIED BY: 

DATE: 9/18/92

**AIR TOXICS LTD.**

SAMPLE NAME: Vent Well

ID#: 9209042-01A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name: 6091007		Date of Collection: 9/1/92		
Dil. Factor: 21		Date of Analysis: 9/10/92		
	MDL	MDL	Amount	Amount
Compound	(ppmv)	(uG/L)	(ppmv)	(uG/L)
Benzene	0.021	0.066	0.050	0.16
Toluene	0.021	0.077	0.069	0.25
Total Xylenes	0.021	0.089	0.39	1.7
Ethyl Benzene	0.021	0.089	0.15	0.64

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Jet Fuel)

File Name: 6091007		Date of Collection: 9/1/92		
Dil. Factor: 21		Date of Analysis: 9/10/92		
	MDL	MDL	Amount	Amount
Compound	(ppmv)	(uG/L)	(ppmv)	(uG/L)
TPH*	0.21	0.84	750	3000

\*TPH referenced to Jet Fuel (MW=156)



**AIR TOXICS LTD.**

SAMPLE NAME: Power Plant MPC Red

ID#: 9209042-02A

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6091008	Date of Collection: 9/1/92	
Dil. Factor:		110	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.11	0.34	Not Detected	Not Detected
Toluene	0.11	0.40	2.0	7.4
Total Xylenes	0.11	0.47	9.1	39
Ethyl Benzene	0.11	0.47	2.0	8.5

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Jet Fuel)

File Name:		6091008	Date of Collection: 9/1/92	
Dil. Factor:		110	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	1.1	4.4	1400	5600

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: MPC Red

ID#: 9209042-03A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

<b>File Name:</b>		<b>6091009</b>	<b>Date of Collection:</b> 9/1/92	
<b>Dil. Factor:</b>		<b>110</b>	<b>Date of Analysis:</b> 9/10/92	
<b>Compound</b>	<b>MDL (ppmv)</b>	<b>MDL (uG/L)</b>	<b>Amount (ppmv)</b>	<b>Amount (uG/L)</b>
Benzene	0.11	0.34	Not Detected	Not Detected
Toluene	0.11	0.40	2.9	11
Total Xylenes	0.11	0.47	0.97	4.1
Ethyl Benzene	0.11	0.47	1.3	5.5

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Jet Fuel)

File Name: 6091009		Date of Collection: 9/1/92		
Dil. Factor: 110		Date of Analysis: 9/10/92		
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	1.1	4.4	1500	6000

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: M-MPB 27.5

ID#: 9209042-04A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6091011	Date of Collection: 9/4/92	
Dil. Factor:		210	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.21	0.66	13	41
Toluene	0.21	0.77	11	40
Total Xylenes	0.21	0.89	3.6	15
Ethyl Benzene	0.21	0.89	0.94	4.0

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Jet Fuel)

File Name:		6091011	Date of Collection: 9/4/92	
Dil. Factor:		210	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	2.1	8.4	2300	9200

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: M-MPA 27.5

ID#: 9209042-05A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6091012	Date of Collection: NP	
Dil. Factor:		530	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.53	1.7	6.0	19
Toluene	0.53	2.0	5.8	21
Total Xylenes	0.53	2.2	3.8	16
Ethyl Benzene	0.53	2.2	0.94	4.0

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Jet Fuel)

File Name:		6091012	Date of Collection: NP	
Dil. Factor:		530	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	5.3	21	3600	14000

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: M Vent Well (Radian)

ID#: 9209042-06A

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6091014		Date of Collection: 9/4/92	
Dil. Factor:		2.2		Date of Analysis: 9/10/92	
	MDL	MDL	Amount	Amount	
Compound	(ppmv)	(uG/L)	(ppmv)	(uG/L)	
Benzene	0.002	0.007	0.082	0.26	
Toluene	0.002	0.008	0.30	1.1	
Total Xylenes	0.002	0.009	0.16	0.68	
Ethyl Benzene	0.002	0.009	0.035	0.15	

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Jet Fuel)

File Name:		6091014		Date of Collection: 9/4/92	
Dil. Factor:		2.2		Date of Analysis: 9/10/92	
Compound		MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*		0.022	0.088	26	100

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: Vent Well

ID#: 9209042-07A

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

<b>File Name:</b>	<b>6091015</b>	<b>Date of Collection:</b> 9/1/92
<b>Dil. Factor:</b>	<b>2.2</b>	<b>Date of Analysis:</b> 9/10/92

Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.002	0.007	0.30	0.94
Toluene	0.002	0.008	0.084	0.31
Total Xylenes	0.002	0.009	0.12	0.51
Ethyl Benzene	0.002	0.009	0.034	0.14

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Jet Fuel)

<b>File Name:</b>	<b>6091015</b>	<b>Date of Collection:</b> 9/1/92
<b>Dil. Factor:</b>	<b>2.2</b>	<b>Date of Analysis:</b> 9/10/92

Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	0.022	0.088	36	140

\*TPH referenced to Jet Fuel (MW=156)

**AIR TOXICS LTD.**

SAMPLE NAME: Power Plant Vent Well

ID#: 9209042-08A

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6091016	Date of Collection: 9/1/92	
Dil. Factor:		2.1	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.002	0.007	0.066	0.21
Toluene	0.002	0.008	0.30	1.1
Total Xylenes	0.002	0.009	1.0	4.2
Ethyl Benzene	0.002	0.009	0.35	1.5

**TOTAL PETROLEUM HYDROCARBONS****GC/FID .**

(Quantitated as Gasoline)

File Name:		6091016	Date of Collection: 9/1/92	
Dil. Factor:		2.1	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	0.021	0.084	190	760

\*TPH referenced to Gasoline (MW=100)

**AIR TOXICS LTD.**

SAMPLE NAME: Monitor Point C blue

ID#: 9209042-09A

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6091017	Date of Collection: 9/1/92	
Dil. Factor:		2.1	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.002	0.007	Not Detected	Not Detected
Toluene	0.002	0.008	0.019	0.070
Total Xylenes	0.002	0.009	0.052	0.22
Ethyl Benzene	0.002	0.009	0.005	0.021

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Gasoline)

File Name:		6091017	Date of Collection: 9/1/92	
Dil. Factor:		2.1	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	0.021	0.084	10	40

\*TPH referenced to Gasoline (MW=100)



**AIR TOXICS LTD.**

SAMPLE NAME: Power Plant MPA Red

ID#: 9209042-10A

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6091018	Date of Collection: 9/1/92	
Dil. Factor:		110	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.11	0.34	Not Detected	Not Detected
Toluene	0.11	0.40	1.1	4.0
Total Xylenes	0.11	0.47	7.4	31
Ethyl Benzene	0.11	0.47	1.8	7.6

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Gasoline)

File Name:		6091018	Date of Collection: 9/1/92	
Dil. Factor:		110	Date of Analysis: 9/10/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	1.1	4.4	1100	4400

\*TPH referenced to Gasoline (MW=100)

**AIR TOXICS LTD.**

SAMPLE NAME: MPA Red, Little or No Vacuum Flow

ID#: 9209042-11A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6091105	Date of Collection: 9/1/92	
Dil. Factor:		2.0	Date of Analysis: 9/11/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.002	0.006	0.014	0.044
Toluene	0.002	0.007	0.033	0.12
Total Xylenes	0.002	0.008	0.22	0.93
Ethyl Benzene	0.002	0.008	0.006	0.025

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Gasoline)

File Name:		6091105	Date of Collection: 9/1/92	
Dil. Factor:		2.0	Date of Analysis: 9/11/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	0.020	0.080	1.4	5.6

\*TPH referenced to Gasoline (MW=100)

**AIR TOXICS LTD.**

SAMPLE NAME: MPA Red

ID#: 9209042-12A

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6091106		Date of Collection: 9/1/92	
Dil. Factor:		520		Date of Analysis: 9/11/92	
	MDL	MDL	Amount	Amount	
Compound	(ppmv)	(uG/L)	(ppmv)	(uG/L)	
Benzene	0.52	1.6	120	370	
Toluene	0.52	1.9	22	81	
Total Xylenes	0.52	2.2	18	76	
Ethyl Benzene	0.52	2.2	6.8	29	

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Gasoline)

File Name:		6091106		Date of Collection: 9/1/92	
Dil. Factor:		520		Date of Analysis: 9/11/92	
	MDL	MDL	Amount	Amount	
Compound	(ppmv)	(uG/L)	(ppmv)	(uG/L)	
TPH*	5.2	21	6700	27000	

\*TPH referenced to Gasoline (MW=100)

**AIR TOXICS LTD.**

SAMPLE NAME: MPA Red Duplicate

ID#: 9209042-12B

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6091107	Date of Collection: 9/1/92	
Dil. Factor:		520	Date of Analysis: 9/11/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.52	1.6	110	340
Toluene	0.52	1.9	22	81
Total Xylenes	0.52	2.2	18	76
Ethyl Benzene	0.52	2.2	6.6	28

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Gasoline)

File Name:		6091107	Date of Collection: 9/1/92	
Dil. Factor:		520	Date of Analysis: 9/11/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	5.2	21	6400	26000

\*TPH referenced to Gasoline (MW=100)

**AIR TOXICS LTD.**

SAMPLE NAME: Method Spike

ID#: 9209042-13A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

<b>File Name:</b>	<b>6091101</b>	<b>Date of Collection:</b>	<b>NA</b>
<b>Dil. Factor:</b>	<b>1.0</b>	<b>Date of Analysis:</b>	<b>9/11/92</b>

	MDL	MDL	
Compound	(ppmv)	(uG/L)	% Recovery
Benzene	0.001	0.003	112
Toluene	0.001	0.004	111
Total Xylenes	0.001	0.004	110
Ethyl Benzene	0.001	0.004	109

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Gasoline)

<b>File Name:</b>	<b>6091102</b>	<b>Date of Collection:</b>	<b>NA</b>
<b>Dil. Factor:</b>	<b>1.0</b>	<b>Date of Analysis:</b>	<b>9/11/92</b>

	MDL	MDL	
Compound	(ppmv)	(uG/L)	% Recovery
TPH*	0.010	0.040	90

\*TPH referenced to Gasoline (MW=100)

**AIR TOXICS LTD.**

SAMPLE NAME: Lab Blank

ID#: 9209042-14A

**EPA Method TO-3**  
(Aromatic Volatile Organics in Air)**BTXE BY GC/PID**

File Name:		6091104	Date of Collection: NA	
Dil. Factor:		1.0	Date of Analysis: 9/11/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.001	0.003	Not Detected	Not Detected
Toluene	0.001	0.004	Not Detected	Not Detected
Total Xylenes	0.001	0.004	Not Detected	Not Detected
Ethyl Benzene	0.001	0.004	Not Detected	Not Detected

**TOTAL PETROLEUM HYDROCARBONS**  
**GC/FID**  
(Quantitated as Gasoline)

File Name:		6091104	Date of Collection: NA	
Dil. Factor:		1.0	Date of Analysis: 9/11/92	
Compound	MDL (ppmv)	MDL (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH*	0.010	0.040	Not Detected	Not Detected

\*TPH referenced to Gasoline (MW=100)

**AIR TOXICS LTD.**

SAMPLE NAME: Lab Blank

ID#: 9209042-14B

**EPA Method TO-3**

(Aromatic Volatile Organics in Air)

**BTXE BY GC/PID**

File Name:		6091004		Date of Collection: NA	
Dil. Factor:		1.0		Date of Analysis: 9/10/92	
	MDL	MDL	Amount	Amount	
Compound	(ppmv)	(uG/L)	(ppmv)	(uG/L)	
Benzene	0.001	0.003	Not Detected	Not Detected	
Toluene	0.001	0.004	Not Detected	Not Detected	
Total Xylenes	0.001	0.004	Not Detected	Not Detected	
Ethyl Benzene	0.001	0.004	Not Detected	Not Detected	

**TOTAL PETROLEUM HYDROCARBONS****GC/FID**

(Quantitated as Gasoline)

File Name:		6091004		Date of Collection: NA	
Dil. Factor:		1.0		Date of Analysis: 9/10/92	
	MDL	MDL	Amount	Amount	
Compound	(ppmv)	(uG/L)	(ppmv)	(uG/L)	
TPH*	0.010	0.040	Not Detected	Not Detected	

\*TPH referenced to Gasoline (MW=100)

[illegible]



**ENGINEERING-SCIENCE, INC.**

RESEARCH AND DEVELOPMENT  
LABORATORY  
600 BANCROFT WAY  
BERKELEY, CALIFORNIA 94710  
(415) 841-7353

310

Report Date: October 9, 1992

Work Order No.: 4269

Client: Jeff Kittel  
Battelle  
505 King Ave.  
Columbus, OH 43201

Date of Sample Receipt: 08/25/92

Your soil samples identified as:

CA-V-4.0  
CA-V-6.0  
CA-V-9.0  
GA1-V-2.5  
GA1-V-5.5  
GA1-V-8.0  
GA2-V-4.0  
GA2-V-5.5  
GA2-V-11.5

were analyzed for BTEX by EPA Method 8020, pH, alkalinity,  
iron, total Kjeldahl nitrogen, moisture, TRPH by EPA Method  
418.1 and total phosphours.

The analytical reports for the samples listed above are  
attached.

**GC VOLATILES DATA PACKAGE**

BTEX CASE NARRATIVE  
WORK ORDER NO. 4269  
EPA METHOD 8020

These nine soil samples were analyzed for benzene, toluene, ethylbenzene, and xylenes (BTEX) by EPA Method 8020. ESBL selected compounds and spiking amounts were used for the surrogates and matrix spike/spike duplicates. ESBL QC acceptance criteria were used for the surrogates; ESBL QC acceptance criteria were used for the matrix spike/spike duplicates.

All analytes found at concentrations greater than ESBL method detection limits were quantitated on a second dissimilar column.

All samples were analyzed within EPA Data Validation Technical Holding Times with the exception of the second column confirmation of sample GA-V-9.0 (4269-3). The primary result was analyzed within holding time.

Six blanks were analyzed with these samples and met method acceptance criteria for surrogates and contamination.

The continuing calibration checks used for quantifying these samples met method acceptance criteria.

All surrogate recoveries were within ESBL acceptance criteria.

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture: 11.23

Client ID: <sup>C TP 9/24</sup>GA-V-4.0

Matrix:SOIL

Laboratory ID:4269-1

Level:LOW

Unit:ug/KG

Dilution Factor: 5


Date Analyzed:08/28/92

Date Confirmed:09/02/92  
-----

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	ND	ND	3.4
Ethyl Benzene	ND	ND	2.8
Toluene	ND	ND	3.9
Xylenes (total)	33.0	90.0	5.1

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST:AB

GROUP LEADER: 

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.: 4269

% Moisture: 5.85

Client ID: <sup>TP 9/24</sup> GA-V-6.0

Matrix: SOIL

Laboratory ID: 4269-2

Level: LOW

Unit: ug/KG

Dilution Factor: 5

Date Analyzed: 08/28/92

Date Confirmed: 09/02/92  
=====

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	ND	ND	3.2
Ethyl Benzene	ND	ND	2.6
Toluene	46.0	740.0	3.7
Xylenes (total)	340.0	470.0	4.8

ND-Not Detected  
NA-Not Applicable  
D-Dilution FactorANALYST: *AS*GROUP LEADER: *Russell*

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture: 19.68

Client ID: <sup>C TP 9/24/92</sup> SA-V-9.0

Matrix:SOIL

Laboratory ID:4269-3

Level:LOW

Unit:ug/KG

Dilution Factor: 2


Date Analyzed:08/28/92

Date Confirmed:09/04/92  
=====

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	43.0	85.0	1.5
Ethyl Benzene	ND	ND	1.2
Toluene	ND	ND	1.7
Xylenes (total)	11.0	92.0	2.2

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST:AB

GROUP LEADER: 

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture: 20.26

Client ID:GA1-V-2.5

Matrix:SOIL

Laboratory ID:4269-4

Level:MEDIUM

Unit:ug/KG

Dilution Factor: 1

Date Analyzed:08/31/92  
Date Confirmed:09/02/92=====ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST:AS

GROUP LEADER:



-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture: 24.84

Client ID:GA1-V-5.5

Matrix:SOIL

Laboratory ID:4269-5

Level:MEDIUM

Unit:ug/KG


Dilution Factor: 1

Date Analyzed:08/31/92  
Date Confirmed:09/02/92  
=====

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	ND	ND	80.0
Ethyl Benzene	ND	ND	66.0
Toluene	850.0	420.0	93.0
Xylenes (total)	4800.0	3000.0	120.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST:AB

GROUP LEADER: 



-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture: 20.71

Client ID:GA1-V-8.0

Matrix:SOIL

Laboratory ID:4269-6

Level:MEDIUM

Unit:ug/KG

Dilution Factor: 1


Date Analyzed:09/03/92

Date Confirmed:09/03/92  
=====

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	ND	ND	76.0
Ethyl Benzene	ND	ND	63.0
Toluene	690.0	480.0	88.0
Xylenes (total)	2700.0	960.0	110.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST:AS

GROUP LEADER: 

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture: 23.5

Client ID:GA2-V-4.0

Matrix:SOIL

Laboratory ID:4269-7

Level:LOW

Unit:ug/KG

Dilution Factor: 1


Date Analyzed:08/28/92

Date Confirmed:NA  
=====

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	ND	ND	0.8
Ethyl Benzene	ND	ND	0.6
Toluene	ND	ND	0.9
Xylenes (total)	ND	ND	1.2

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST: AB

GROUP LEADER: 

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture: 22.57

Client ID:GA2-V-5.5

Matrix:SOIL

Laboratory ID:4269-8

Level:LOW

Unit:ug/KG


Dilution Factor: 1

Date Analyzed:08/28/92  
Date Confirmed:NA-----

Compound	Primary Result	Confirmatory Result	Reporting Limit
=====			
Benzene	ND	ND	0.8
Ethyl Benzene	ND	ND	0.6
Toluene	ND	ND	0.9
Xylenes (total)	ND	ND	1.2

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST: AB

GROUP LEADER: 

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture: 20.47

Client ID:GA2-V-11.5

Matrix:SOIL

Laboratory ID:4269-9

Level:LOW

Unit:ug/KG

Dilution Factor: 1

Date Analyzed:08/28/92

Date Confirmed:NA  
=====

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	ND	ND	0.8
Ethyl Benzene	ND	ND	0.6
Toluene	ND	ND	0.9
Xylenes (total)	ND	ND	1.1

ND-Not Detected  
NA-Not Applicable  
D-Dilution FactorANALYST: *AB*GROUP LEADER: *[Signature]*

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture: 0

Client ID:(BLANK)

Matrix:SOIL

Laboratory ID:MSVG3920902B

Level:NA

Sample wt./vol : 5 gm.

Unit:ug/Kg

Dilution Factor: 1

Date Analyzed:09-02-92

Date Confirmed:NA  
=====

Compound

Result

Reporting  
Limit  
=====

Benzene

ND

0.8

Ethyl Benzene

ND

0.6

Toluene

ND

0.9

Xylenes (total)

ND

1.2

ND-Not Detected  
NA-Not Applicable  
D-Dilution FactorANALYST: *Am F*GROUP LEADER: *Perov*

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture:NA

Client ID:METHOD BLANK

Matrix:SOIL

Laboratory ID:MWVG3920902B

Level:MEDIUM

Unit:ug/KG

Dilution Factor: 1


Date Analyzed:09/02/92

Date Confirmed:NA  
=====

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	ND	ND	60.0
Ethyl Benzene	ND	ND	50.0
Toluene	ND	ND	70.0
Xylenes (total)	ND	ND	90.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST: AM

GROUP LEADER: 

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture:NA

Client ID:METHOD BLANK

Matrix:SOIL

Laboratory ID:MWVG5920903

Level:MEDIUM

Unit:ug/KG

Dilution Factor: 1

Date Analyzed:09/03/92

Date Confirmed:NA  
-----

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	ND	ND	60.0
Ethyl Benzene	ND	ND	50.0
Toluene	ND	ND	70.0
Xylenes (total)	ND	ND	90.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution FactorANALYST: *AB*GROUP LEADER: *[Signature]*

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture:NA

Client ID:METHOD BLANK

Matrix:SOIL

Laboratory ID:MWVG3920903B

Level:MEDIUM

Unit:ug/KG

Dilution Factor: 1

Date Analyzed:09/03/92

Date Confirmed:NA  
=====

Compound	Primary Result	Confirmatory Result	Reportin Limit
Benzene	ND	ND	60.0
Ethyl Benzene	ND	ND	50.0
Toluene	ND	ND	70.0
Xylenes (total)	ND	ND	90.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST:AMB

GROUP LEADER:





-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture:NA

Client ID:METHOD BLANK

Matrix:SOIL

Laboratory ID:MWVG3920904B

Level:MEDIUM

Unit:ug/KG

Dilution Factor: 1

Date Analyzed:09/04/92

Date Confirmed:NA  
=====

Compound	Primary Result	Confirmatory Result	Reportin Limit
Benzene	ND	ND	60.0
Ethyl Benzene	ND	ND	50.0
Toluene	ND	ND	70.0
Xylenes (total)	ND	ND	90.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution FactorANALYST: *AS*GROUP LEADER: *kw*

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture:NA

Client ID:METHOD BLANK

Matrix:SOIL

Laboratory ID:MSVG5920828

Level:LOW

Unit:ug/KG

Dilution Factor: 1

Date Analyzed:08/28/92  
Date Confirmed:NA

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	ND	ND	0.6
Ethyl Benzene	ND	ND	0.5
Toluene	ND	ND	0.7
Xylenes (total)	ND	ND	0.9

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST:AB

GROUP LEADER:

-----  
GC ANALYTICAL REPORT  
Analytical Method  
8020 Aromatic Compounds

Work Order NO.:4269

% Moisture:NA

Client ID:METHOD BLANK

Matrix:SOIL

Laboratory ID:MWVG5920831

Level:MEDIUM

Unit:ug/KG


Dilution Factor: 1

Date Analyzed:08/31/92  
Date Confirmed:NA

Compound	Primary Result	Confirmatory Result	Reporting Limit
Benzene	ND	ND	60.0
Ethyl Benzene	ND	ND	50.0
Toluene	ND	ND	70.0
Xylenes (total)	ND	ND	90.0

ND-Not Detected  
NA-Not Applicable  
D-Dilution Factor

ANALYST: AB

GROUP LEADER: 

-----  
ES-ENGINEERING SCIENCE, INC.

600 BANCROFT WAY  
BERKELEY, CA 94710  
-----

GC ANALYTICAL REPORT  
ANALYTICAL REPORT  
BTEX AROMATIC COMPOUNDS

MATRIX: MEDIUM SOIL

COLUMN ID: VGC-5 DB-624

DATE: 08/31/92 &  
09/03/92  
=====

LABORATORY NO.

CLIENT ID

a-a-a-TriFluoro  
Toluene  
=====

MWVG5920831

METHOD BLANK

101

MWVG5920903

METHOD BLANK

99

4269-4

GA1-V-2.5

116

4269-5

GA1-V-5.5

130

4269-6

GA1-V-8.0

130

ES-ENGINEERING SCIENCE, INC.

600 BANCROFT WAY  
BERKELEY, CA 94710

GC ANALYTICAL REPORT  
ANALYTICAL REPORT  
BTEX AROMATIC COMPOUNDS

MATRIX: SOIL

COLUMN ID: VGC-5 DB-624

DATE: 08/28/92

LABORATORY NO.

CLIENT ID

a-a-a-TriFluoro  
Toluene

MSVG5920828

METHOD BLANK

104

4269-1

CA-V-4.0

126

4269-2

CA-V-6.0

122

4269-3

CA-V-9.0

117

4269-7

GA2-V-4.0

117

4269-8

GA2-V-5.5

117

4269-9

GA2-V-11.5

110

ES-ENGINEERING SCIENCE, INC.

600 BANCROFT WAY  
BERKELEY, CA 94710

GC ANALYTICAL REPORT  
ANALYTICAL REPORT  
BTEX AROMATIC COMPOUNDS

<sup>TP 9/24</sup>  
MATRIX: ~~MEDIUM~~ SOIL

COLUMN ID: VGC-3 VOCOL

DATE: 09/02-04/92

LABORATORY NO.

CLIENT ID

a-a-a-TriFluoro  
Toluene

MWVG3920902A	METHOD BLANK	114
MWVG3920903B	METHOD BLANK	103
MWVG3920904B	METHOD BLANK	118
SWVG3920902A	SPIKE	106
SWVG3920902B	SPIKE DUPLICATE	105
4269-1	CA-V-4.0	104
4269-2	CA-V-6.0	72
4269-4	GA1-V-2.5	54
4269-5	GA1-V-5.5	51
4269-3	CA-V-9.0	116
4269-6	GA1-V-8.0	78

# METHOD BLANK SUMMARY

WO # 4269

LAB NAME : ENGINEERING-SCIENCE, INC.

DATE ANALYZED : 08/31/92 &  
: 09/03/92

LAB SAMPLE ID: MWVG5920831(0903)

DATE EXTRACTED : NA

MATRIX : MEDIUM SOIL

INSTRUMENT ID: VGC-5

LAB SAMPLE ID	CLIENT SAMPLE ID	DATE ANALYZED
MWVG5920831	METHOD BLANK	08/31/92
4269-4	GA1-V-2.5	08/31/92
4269-5	GA1-V-5.5	08/31/92
4269-6	GA1-V-8.0	09/03/92
MWVG5920903	METHOD BLANK	09/03/92

# METHOD BLANK SUMMARY

WO # 4269

LAB NAME : ENGINEERING-SCIENCE, INC.

DATE ANALYZED : 08/28/92

LAB SAMPLE ID:MSVG5920828

DATE EXTRACTED : NA

MATRIX :SOIL

INSTRUMENT ID:VGC-5

LAB SAMPLE ID	CLIENT SAMPLE ID	DATE ANALYZED
-----	-----	-----
MSVG5920828	METHOD BLANK	08/28/92
4269-1	CA-V-4.0	08/28/92
4269-2	CA-V-6.0	08/28/92
4269-3	CA-V-9.0	08/28/92
4269-7	GA2-V-4.0	08/28/92
4269-8	GA2-V-5.5	08/28/92
4269-9	GA2-V-11.5	08/28/92



# METHOD BLANK SUMMARY

WO # 4269

LAB NAME : ENGINEERING-SCIENCE, INC.

DATE ANALYZED : 09/02-04/92

LAB SAMPLE ID: MWVG39209(02-04)

DATE EXTRACTED : NA

MATRIX : <sup>TP 9/24</sup>~~MEDIUM~~ SOIL

INSTRUMENT ID: VGC-3

LAB SAMPLE ID	CLIENT SAMPLE ID	DATE ANALYZED
MWVG3920902B	METHOD BLANK	09/02/92
MWVG3920903B	METHOD BLANK	09/03/92
MWVG3920904B	METHOD BLANK	09/04/92
SWVG3920902A	SPIKE	09/02/92
SWVG3920902B	SPIKE DUPLICATE	09/02/92
4269-1	CA-V-4.0	09/02/92
4269-2	CA-V-6.0	09/02/92
4269-3	CA-V-9.0	09/04/92
4269-4	GA1-V-5.5	09/02/92
4269-5	GA1-V-5.5	09/02/92
4269-6	GA1-V-8.0	09/03/92

**TOTAL RECOVERABLE PETROLEUM HYDROCARBONS  
DATA PACKAGE**

CASE NARRATIVE  
WORK ORDER NO.4269  
TRPH - 418.1 SOILS

Samples CA-V-4.0 (4269-01), CA-V-6.0 (4269-02) and CA-V-9.0 (4269-03) were analyzed six days past holding time.

Samples GA1-V-2.5 (4269-04), GA1-V-5.5 (4269-05) and GA1-V-8.0 (4269-06) were analyzed five days past holding time.

Samples GA2-V-4.0 (4269-07), GA2-V-5.5 (4269-08) and GA2-V-11.5 (4269-09) were analyzed four days past holding time.

All samples were extracted within the 28 day extraction period.

ES-ENGINEERING SCIENCE, INC.

600 Bancroft Way  
Berkeley, CA 94710

ORGANIC ANALYTICAL REPORT

Work Order NO.: 4269

Matrix: Soil

Parameter: TPH

Unit: mg/Kg

Analytical

Method: 418.1

Date Extracted: 09/15/92

QC Batch NO.: S92QCB022TPH

Date Analyzed: 09/22/92


Sample ID:	Client ID:	Result	Reporting Limit	Percent Moisture
4269-01	GA-V-4.0	180	5	11.2
4269-02	GA-V-6.0	1700	4	5.9
4269-03	GA-V-9.0	390	5	19.7
4269-04	GA1-V-2.5	420	5	20.3
4269-05	GA1-V-5.5	300	5	24.8
4269-06	GA1-V-8.0	85	5	20.7
4269-07	GA2-V-4.0	51	5	23.5
4269-08	GA2-V-5.5	61	5	22.6
4269-09	GA2-V-11.5	180	5	20.5
MSTPH920915	METHOD BLANK	ND	4	NA

NA\_ Not Analyzed  
ND\_ Not Detected

ANALYST:

GROUP LEADER:





ES-ENGINEERING SCIENCE, INC.

600 Bancroft Way  
Berkeley. CA 94710

=====

ORGANIC QUALITY CONTROL RESULTS SUMMARY  
Blank Spike/Spike Duplicate

Work Order NO.: 4269

QC Sample NO.: SSTPH920903A & B

Analytical Method: 418.1

Blank I.D.: MSTPH920903

Matrix: Soil

QC Batch NO.: S92QCB022TPH

Unit: mg/Kg

=====

Parameter	Date Analyzed	BR	SA	BS	PR	BSD	PR	RPD
TPH	09/04/92	0	165	176	107	176	107	0

=====

BS-Blank Spike  
BSD-Blank Spike Duplicate  
SA-Spike Added  
BR\_Blank Result  
NA-Not Applicable  
NC-Not Calculated  
ND-Not Detected

$$RPD = ((BS - BSD) / ((BS + BSD) / 2)) * 100$$

$$PR = ((BS \text{ OR } BSD - BR) / SA) * 100$$

ANALYST:

QUALITY CONTROL:

-----  
*Alan J*

-----  
*MM3*

**INORGANICS DATA PACKAGE**

## INORGANICS ANALYTICAL REPORT

Client: ES-Denver  
Project: BattelleWork Order: 4269  
Matrix: Solid

Client's ID: CA-V-4.0 CA-V-6.0 CA-V-9.0

Sample Date: 08/19/92 08/19/92 08/19/92

% Moisture:

Lab ID: 4269.01 4269.02 4269.03

Parameter	-----Results-----	Method	Normal Report Limit	Units	Date Analyzed
Alkalinity	230. 190. 490.	SM 403(M)	50	mg/Kg CaCO3	09/04/92
Moisture	11.2 5.9 19.7	ASTM D2216	.1	% by wt	09/04/92
pH	8.3 8.3 7.6	EPA 9045	NA	pH Units	08/28/92

Note: Samples for alkalinity analysis were extracted using 10mL water for each 1g sample. These water extracts were analyzed for alkalinity, and the results were calculated in the solid on a dry-weight basis.

NA- Not Applicable

ND- Not Detected

ANALYST: Don MeatorGROUP LEADER: William S. Lee

## INORGANICS ANALYTICAL REPORT

Client: ES-Denver  
Project: BattelleWork Order: 4269  
Matrix: Solid

Client's ID: GA1-V-2.5 GA1-V-5.5 GA1-V-8.0

Sample Date: 08/20/92 08/20/92 08/20/92  
% Moisture:  
Lab ID: 4269.04 4269.05 4269.06

Parameter	-----Results-----	Method	Normal Report Limit	Units	Date Analyzed
Alkalinity	400. 670. 500.	SM 403(M)	50	mg/Kg CaCO3	09/04/92
Moisture	20.3 24.8 20.7	ASTM D2216	.1	% by wt	09/04/92
pH	7.8 7.4 7.4	EPA 9045	NA	pH Units	08/28/92

Note: Samples for alkalinity analysis were extracted using 10mL water for each 1g sample. These water extracts were analyzed for alkalinity, and the results were calculated in the solid on a dry-weight basis.

NA- Not Applicable  
ND- Not DetectedANALYST: Don PleatorGROUP LEADER: 



## INORGANICS ANALYTICAL REPORT

Client: ES-Denver  
Project: BattelleWork Order: 4269  
Matrix: Solid

Client's ID: GA2-V-4.0 GA2-V-5.5 GA2-V-11.5

Sample Date: 08/21/92 08/21/92 08/21/92

% Moisture:

Lab ID: 4269.07 4269.08 4269.09

Parameter	-----Results-----	Method	Normal Report Limit	Units	Date Analyzed
Alkalinity	480. 500. 500.	SM 403(M)	50	mg/Kg CaCO3	09/04/92
Moisture	23.5 22.6 20.5	ASTM D2216	.1	% by wt	09/04/92
pH	7.7 7.8 7.8	EPA 9045	NA	pH Units	08/28/92

Note: Samples for alkalinity analysis were extracted using 10mL water for each 1g sample. These water extracts were analyzed for alkalinity, and the results were calculated in the solid on a dry-weight basis.

NA- Not Applicable

ND- Not Detected

ANALYST: Don CleatorGROUP LEADER: William S. Dwyer

## INORGANICS ANALYTICAL REPORT

Client: ES-Denver  
Project: BattelleWork Order: 4269  
Matrix: SolidClient's ID: Prep  
Blank

Sample Date:

% Moisture:

Lab ID: Prep Blank

Parameter	-----Results-----	Method	Normal Report Limit	Units	Date Analyzed
Alkalinity	ND	SM 403(M)	50	mg/Kg CaCO <sub>3</sub>	09/04/92
Moisture	NA	ASTM D2216	.1	% by wt	09/04/92
pH	NA	EPA 9045	NA	pH Units	08/28/92

Note: Samples for alkalinity analysis were extracted using 10mL water for each 1g sample. These water extracts were analyzed for alkalinity, and the results were calculated in the solid on a dry-weight basis.

NA- Not Applicable

ND- Not Detected

ANALYST: Don SleatorGROUP LEADER: Walter J. [Signature]

## INORGANICS QC SUMMARY - LAB CONTROL SAMPLE

Work Order: 4269 % Moisture: NA  
Lab ID of LCS: Matrix: Solid  
Alkalinity: 452.20 LCS  
Units: mg/Kg CaCO3

Parameter	Date Analyzed LCS	LCS Result	Conc Added	% Rec LCS	Advisory Limits	
					-- % Rec -- Low	High
Alkalinity	09/04/92	23050.00	23650.00	97	80	120

ANALYST: Don SleatorDate 9/09/92REVIEWER: STDate 9/16/92

File: M1QCLCSW

## INORGANIC QC SUMMARY - MS and MSD

Work Order: 4269

% Moisture: NA

Alkalinity Moisture pH  
 Lab ID Spk/Dup: Blank Spk 4269.01 4254.01  
 QC Batch: 452.21 451.50 453.30

Matrix: Solid  
 Units: mg/Kg CaCO3 (Alk)  
 % by wt. (Mois)  
 pH Units (pH)

Parameter	Date Analyzed MS/Dup	-----Results-----			RPD	RPD QC Limit	-Conc Added-		Percent Recovered	
		Unspiked Sample	MS/Sample	MSD/Dup			MS	MSD	MS	MSD
Alkalinity	09/04/92	0.00	23050.00	23100.00	0	20	23650.00	23650.00	97	98
Moisture	09/04/92		11.23	11.05	2	20				
pH	08/28/92		8.11	8.06	1	20				

\* or N = Outside QC Limit:

QC Limits for % Rec: 75 - 125

ANALYST: Don ElestonDate 9/09/92REVIEWER: SHDate 9/10/92

File: M1QCKSWH

**METALS DATA PACKAGE**

CASE NARRATIVE  
WORK ORDER NO.4269  
METALS-SOILS

The concentration of iron in sample N3V6-7 was greater than four times the spike added to the MS and MSD samples. The LCS and duplicate LCS results for iron were checked, and the laboratory was found to be in control. All iron results in this batch are therefore reported unqualified based on matrix spike recovery.

Client ID's were abridged by the laboratory to facilitate computer entry of analytical data. The following should be used as a reference:

<u>CLIENT ID</u>	<u>ABRIDGED ID</u>
CA-V-4.0	CA40
CA-V-6.0	CA60
CA-V-9.0	CA90
GA1-V-2.5	GA125
GA1-V-5.5	GA155
GA1-V-8.0	GA180
GA2-V-4.0	GA240
GA2-V-5.5	GA255
GA2-V-11.5	GA2115

CLIENT SAMPLE ID

## CA40

Solids: 88.8

Concentration Units (ug/L or mg/kg dry weight): MG/KG

[illegible]**Comments:**

CLIENT SAMPLE ID

## CA60

Solids: 94.2

Concentration Units (ug/L or mg/kg dry weight): MG/KG

[illegible]

Comments:



CLIENT SAMPLE ID

## CA90

## INORGANIC ANALYSES DATA SHEET

GA125

CLIENT SAMPLE ID

## GA155

Concentration Units (ug/L or mg/kg dry weight): MG/KG

[illegible]

Comments:



CLIENT SAMPLE ID

## GA240

CLIENT SAMPLE ID

## GA255

CLIENT SAMPLE ID

## GA2115

CLIENT SAMPLE ID

## PBLANK

Lab Code: ESBL\_\_\_\_\_ Case No.: 4254S SAS No.: \_\_\_\_\_ SDG No.: CA40\_\_\_\_\_

Lab Sample ID: PBK 460.94

Date Received: 09/01/92

Solids: 100.0

Concentration Units (ug/L or mg/kg dry weight): MG/KG

[illegible]

Comments:



CLIENT SAMPLE ID

N3V6-7S2

Contract: AFCEE

SDG No.: CA40

Level (low/med): LOW

Solids for Sample: 85.4

Concentration Units (ug/L or mg/kg dry weight):MG/KG

omments:

CLIENT SAMPLE ID

N3V6-7S1

Contract: AFCEE

SAS No. :

SDG No.: CA40\_\_\_\_\_

Level (low/med): LOW\_\_

Concentration Units (ug/L or mg/kg dry weight):MG/KG

[illegible]

Comments:

CLIENT SAMPLE ID

MATRIX SPIKE DUPLICATE

N3V6-7SD

Lab Code: ESBL Case No.: 4254S SAS No.: SDG No.: CA40

Matrix (soil/water): SOIL\_ Level (low/med): \_LOW\_

Solids for Sample: 85.4 % Solids for Duplicate: 85.6

Concentration Units (ug/L or mg/kg dry weight):MG/KG

[illegible]

## BLANK SPIKE SAMPLE

Contract: AFCEE\_\_\_\_\_

SDG No.: CA40

Aqueous LCS Source: \_\_\_\_\_

3/90

## BLANK SPIKE SAMPLE

Aqueous LCS Source: \_\_\_\_\_

3/90

CLIENT SAMPLE ID

BLANK SPIKE DUPLICATE

LCSSD

Lab Name: E S BERKELEY LABORATORY Contract: AFCEE

Lab Code: ESBL Case No.: 4254S SAS No.: SDG No.: CA40

Matrix (soil/water): SOIL\_ Level (low/med): \_LOW\_

Solids for Sample: 100.0 % Solids for Duplicate: 100.0

Concentration Units (ug/L or mg/kg as received):MG/KG

[illegible]

## ICP SERIAL DILUTION

Lab Name: E S BERKELEY LABORATORY Contract: AFCEE

N3V6-7L

Lab Code: ESDL Case No.: 4254S SAS No.: SDG No.: CA40

Matrix (soil/water): SOIL\_ Level (low/med): LOW\_

Concentration Units: ug/L

[illegible]

100

1. The first part of the document is a list of names and addresses, which appears to be a directory or a list of contacts. The names are written in a cursive script, and the addresses are listed below them.

2. The second part of the document is a list of names and addresses, which appears to be a directory or a list of contacts. The names are written in a cursive script, and the addresses are listed below them.

3. The third part of the document is a list of names and addresses, which appears to be a directory or a list of contacts. The names are written in a cursive script, and the addresses are listed below them.

4. The fourth part of the document is a list of names and addresses, which appears to be a directory or a list of contacts. The names are written in a cursive script, and the addresses are listed below them.

5. The fifth part of the document is a list of names and addresses, which appears to be a directory or a list of contacts. The names are written in a cursive script, and the addresses are listed below them.

6. The sixth part of the document is a list of names and addresses, which appears to be a directory or a list of contacts. The names are written in a cursive script, and the addresses are listed below them.

7. The seventh part of the document is a list of names and addresses, which appears to be a directory or a list of contacts. The names are written in a cursive script, and the addresses are listed below them.

8. The eighth part of the document is a list of names and addresses, which appears to be a directory or a list of contacts. The names are written in a cursive script, and the addresses are listed below them.

9. The ninth part of the document is a list of names and addresses, which appears to be a directory or a list of contacts. The names are written in a cursive script, and the addresses are listed below them.

10. The tenth part of the document is a list of names and addresses, which appears to be a directory or a list of contacts. The names are written in a cursive script, and the addresses are listed below them.

Lab Name: E S BERKELEY LABORATORY Contract: AFCEE

Lab Code: ESBL Case No.: 4254S SAS No.: SDG No.: CA40

ICP ID Number: TJA 61 M Date: 09/01/92

Frame AA ID Number : \_\_\_\_\_ Matrix: SOIL\_

Furnace AA ID Number : \_\_\_\_\_ (ug/L in 1.00g to 100ml digestate)

[illegible]

Comments:

FORM X - IN

ILMO2.





Contract: AFCEE\_\_\_\_\_

SAS No. : \_\_\_\_\_ SDG No. : CA40

Method: P\_

End Date: 09/03/92

FORM XIV - IN

## Inorganics Report

## ANALYSIS RUN LOG

Lab Name: E\_S\_BERKELEY\_LABORATORY\_

Contract: AFCEE\_

Lab Code: ESBL\_ Case No.: 4254S\_

SAS No.: \_ SDG No.: CA40\_

Instrument ID Number: TJA 61 M\_

Method: P\_

Start Date: 09/03/92

End Date: 09/03/92

EPA Sample No.	D/F	Time	% R	Analytes																	
				F																	
TD1	1.00	1728		X																	
STD2	1.00	1732		X																	
TD3	1.00	1737		X																	
TD4	1.00	1742		X																	
ICV	1.00	1746		X																	
ICB	1.00	1751		X																	
CSA	1.00	1756		X																	
CSAB	1.00	1800		X																	
CRI	1.00	1805																			
BLANK	1.00	1809		X																	
ZZZZZ	1.00	1814																			
LCSS	1.00	1819		X																	
ESSD	1.00	1823		X																	
N3V6-7	1.00	1828		X																	
N3V6-7S1	1.00	1832		X																	
N3V6-7S2	1.00	1837		X																	
QIV	1.00	1842		X																	
CCB	1.00	1846		X																	
N3V6-7L	1.00	1851		X																	
MA2-3	1.00	1855		X																	
MA6-7	1.00	1900		X																	
CA40	1.00	1905		X																	
G160	1.00	1909		X																	
Q90	1.00	1914		X																	
GA125	1.00	1919		X																	
GA155	1.00	1923		X																	
QIV	1.00	1928		X																	
CCB	1.00	1932		X																	
GA180	1.00	1937		X																	
G240	1.00	1942		X																	
G255	1.00	1946		X																	
GA2115	1.00	1951		X																	

TOTAL KJELDAHL NITROGEN

TOTAL PHOSPHATE

DATA PACKAGE



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4269  
Sample Descript: Soil  
Analysis for: Total Kjeldahl Nitrogen  
First Sample #: 208-4341

Sampled: 8/19-21/92  
Received: Aug 26, 1992  
Analyzed: Sep 3, 1992  
Reported: Sep 17, 1992

## LABORATORY ANALYSIS FOR: Total Kjeldahl Nitrogen

Sample Number	Sample Description	Detection Limit mg/kg	Sample Result mg/kg
208-4341	CAV-4	20	510
208-4342	CAV-6	20	430
208-4343	CAV-9	20	1,200
208-4344	GA1-V-2.5	20	800
208-4345	GA1-V-5.5	20	800
208-4346	GA1-V-8.0	20	800
208-4347	GA2-V-4	20	700
208-4348	GA-V-5.5	20	670
208-4349	GA2-V-11.5	20	490
-	Method Blank	20	N.D.

**THIS REPORT HAS BEEN  
APPROVED AND REVIEWED BY**

*Paulson* 10/5/92  
ESBL PROJECT MANAGER DATE

Analytes reported as N.D. were not present above the stated limit of detection.

SEQUOIA ANALYTICAL

*Tod Granicher*  
Tod Granicher  
Project Manager

**Please Note:**

Analysis results reported on a dry-weight basis.

This report amended 9/23/92.

2084341.ENG <1>



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4269  
Sample Descript: Soil  
Analysis for: Total Phosphorous  
First Sample #: 208-4341

Sampled: 8/19-21/92  
Received: Aug 26, 1992  
Analyzed: Sep 15, 1992  
Reported: Sep 17, 1992

## LABORATORY ANALYSIS FOR: Total Phosphorous

Sample Number	Sample Description	Detection Limit mg/kg	Sample Result mg/kg
208-4341	CAV-4	10	510
208-4342	CAV-6	10	510
208-4343	CAV-9	10	690
208-4344	GA1-V-2.5	10	670
208-4345	GA1-V-5.5	10	720
208-4346	GA1-V-8.0	10	790
208-4347	GA2-V-4	10	750
208-4348	GA-V-5.5	10	650
208-4349	GA2-V-11.5	10	720
-	Method Blank	10	N.D.

Analytes reported as N.D. were not present above the stated limit of detection.

SEQUOIA ANALYTICAL

  
Tod Granicher  
Project Manager

Please Note:

Analysis results reported on a dry-weight basis.

2084341.ENG <2>



# SEQUOIA ANALYTICAL

680 Chesapeake Drive • Redwood City, CA 94063  
(415) 364-9600 • FAX (415) 364-9233

Engineering Science, Inc.  
600 Bancroft Way  
Berkeley, CA 94710  
Attention: Tom Paulson

Client Project ID: W.O. #4269

QC Sample Group: 2084341-49

Reported: Sep 17, 1992

## QUALITY CONTROL DATA REPORT

ANALYTE	Total Kjeldahl	Total
	Nitrogen	Phosphorous

Method:	EPA351.4	EPA365.3
Analyst:	G. Kern	K. Follett
Reporting Units:	mg/kg	mg/kg
Date Analyzed:	Sep 3, 1992	Sep 12, 1992
QC Sample #:	209-0162	208-3561

Sample Conc.:	84	210
---------------	----	-----

Spike Conc. Added:	4000	100
-----------------------	------	-----

Conc. Matrix Spike:	4600	330
------------------------	------	-----

Matrix Spike % Recovery:	113	120
-----------------------------	-----	-----

Conc. Matrix Spike Dup.:	4600	350
-----------------------------	------	-----

Matrix Spike Duplicate % Recovery:	113	140
--	-----	-----

Relative % Difference:	0.0	5.9
---------------------------	-----	-----

SEQUOIA ANALYTICAL

  
Tod Granicher  
Project Manager

% Recovery:	$\frac{\text{Conc. of M.S.} - \text{Conc. of Sample}}{\text{Spike Conc. Added}} \times 100$
Relative % Difference:	$\frac{\text{Conc. of M.S.} - \text{Conc. of M.S.D.}}{(\text{Conc. of M.S.} + \text{Conc. of M.S.D.}) / 2} \times 100$

2084341.ENG <3>



**Battelle**  
Columbus Laboratories

## CHAIN OF CUSTODY RECORD

Form No.

Proj. No.	Project Title	SAMPLE TYPE (✓)		Number of Containers	Remarks
54468-0655	Bioremediation Initiative; Gubern and Campion AFS's, AK.	Container No.			
54468-0655	Bioremediation Initiative; Gubern and Campion AFS's, AK.				
SAMPLERS: (Signature) <i>[Signature]</i> 64-424-6122					
DATE	TIME	SAMPLE I.D.			
8/20/92	5:00pm	GA1-V-8.0	✓	1-402	PH, Alkalinity, Soil moisture
8/21/92	10:15 am	GA2-V-4.0	✓	1 brs slv	BTEX, TPH
8/21/92	10:15	GA2-V-4.0	✓	1-1602	TKN, TP
8/21/92	10:15	GA2-V-4.0	✓	1-402	PH, Alkalinity, Soil moisture
8/21/92	10:15	GA2-V-5.5	✓	1 brs slv	BTEX, TPH
8/21/92	10:15	GA2-V-5.5	✓	1-1602	TKN, TP
8/21/92	10:15	GA2-V-5.5	✓	1-402	PH, Alkalinity, Soil moisture
8/21/92	10:15	GA2-V-11.5	✓	1 brs slv	BTEX, TPH
8/21/92	10:15	GA2-V-11.5	✓	1-1602	TKN, TP
8/21/92	10:15	GA2-V-11.5	✓	1-402	PH, Alkalinity, Soil moisture
Relinquished by: (Signature) <i>[Signature]</i> Received by: (Signature) <i>[Signature]</i> Date/Time 8/21/92 11:00					
Relinquished by: (Signature) <i>[Signature]</i> Received by: (Signature) <i>[Signature]</i> Date/Time 8/21/92 11:00					
Relinquished by: (Signature) <i>[Signature]</i> Received for Laboratory by: (Signature) <i>[Signature]</i> Date/Time 8/21/92 11:00					



Proj. No. G4463-0055  
 Bioventing Initiative, Galena  
 and Campion AFS's, AK  
 Job No. DE288

SAMPLERS: (Signature) Jeff DeWitt (614) 424-6122

DATE	TIME	SAMPLE I.D.	SAMPLE TYPE (✓)			Container No.	Number of Containers	Remarks
			Soil	Soil	Soil			
8/19/92	2:00 pm	CA-V-4.0	✓				1 brs slv.	BTEX, TPH
8/19/92	2:00 pm	CA-V-4.0		✓			1-16 oz	TKN, TPH
8/19/92	2:00 pm	CA-V-4.0			✓		1-4 oz	PH, Alkalinity, Iron, S
8/19/92	2:00 pm	CA-V-6.0	✓				1 brs slv.	BTEX, TPH
8/19/92	2:00 pm	CA-V-6.0		✓			1-16 oz	TKN, TPH
8/19/92	2:00 pm	CA-V-6.0			✓		1-4 oz	PH, Alkalinity, Iron, S
8/19/92	2:00 pm	CA-V-9.0	✓				1 brs slv.	BTEX, TPH
8/19/92	2:00 pm	CA-V-9.0		✓			1-16 oz	TKN, TPH
8/19/92	2:00 pm	CA-V-9.0			✓		1-4 oz	PH, Alkalinity, Iron, S
8/19/92	2:00 pm	CA-V-9.0	✓				1 brs slv.	BTEX, TPH
8/19/92	2:00 pm	CA-V-9.0		✓			1-16 oz	TKN, TPH
8/19/92	2:00 pm	CA-V-9.0			✓		1-4 oz	PH, Alkalinity, Iron, S
8/20/92	5:00 pm	GA1-V-2.5	✓				1 brs slv.	BTEX, TPH
8/20/92	5:00 pm	GA1-V-2.5		✓			1-16 oz	TKN, TPH
8/20/92	5:00 pm	GA1-V-2.5			✓		1-4 oz	PH, Alkalinity, Iron, S
8/20/92	5:00 pm	GA1-V-5.5	✓				1 brs slv.	BTEX, TPH
8/20/92	5:00 pm	GA1-V-5.5		✓			1-16 oz	TKN, TPH
8/20/92	5:00 pm	GA1-V-5.5			✓		1-4 oz	PH, Alkalinity, Iron, S
8/20/92	5:00 pm	GA1-V-8.0	✓				1 brs slv.	BTEX, TPH
8/20/92	5:00 pm	GA1-V-8.0		✓			1-16 oz	TKN, TPH

Relinquished by: (Signature)	Date/Time	Received by: (Signature)	Relinquished by: (Signature)	Date/Time	Received by: (Signature)
Jeff DeWitt	8/21/92 11:00				
Relinquished by: (Signature)	Date/Time	Received by: (Signature)	Relinquished by: (Signature)	Date/Time	Received by: (Signature)

Relinquished by: (Signature)	Date/Time	Received for Laboratory by: (Signature)	Date/Time	Remarks
		Jeff DeWitt	08/25/92 0910	
Relinquished by: (Signature)	Date/Time	Received for Laboratory by: (Signature)	Date/Time	Remarks

# ENGINEERING-SCIENCE

## CHAIN OF CUSTODY RECORD

ES JOB NO.	PROJECT NAME/LOCATION 4269	PRESERVATIVES REQUIRED												SHIP TO:
FIELD CONTACT:		ANALYSES REQUIRED												REMARKS
SAMPLERS NAMES & SIGNATURES <i>Ed de la Cruz</i> E														
DATE	TIME	FIELD SAMPLE IDENTIFIER												
8/19/92	2:00	CAV-4. (4269.01C.)									2084341			
8/19/92	2:00	CAV-6. (4269.02C.)									42			
8/19/92	2:00	CAV-9 (4269.03C.)									43			
8/20/92	5:00	GA1-V-2.5 (4269.04C.)									44			
8/20/92	5:00	GA1-V-5.5 (4269.05C.)									45			
8/20/92	5:00	GA1-V-8.0 (4269.06C.)									46			
8/21/92	10:15	GA2-V-4 (4269.07C.)									47			
8/21/92	10:15	GA - V-5.5 (4269.08C.)									48			
8/21/92	10:15	GA2-V-11.5 (4269.09C.)									49			

FIELD CUSTODY RELINQUISHED BY: *Ed de la Cruz* DATE: 8/26/92 TIME: 10:15  
 SHIPPED VIA: AIRBILL # ON RECEIPT: CUSTODY SEALS? ; TEMP: °C  
 RECEIVED FOR LABORATORY BY: *Ed de la Cruz* DATE: 8/26/92 TIME: 10:20 AM  
 PERMANENT FILED BY: *Ed de la Cruz* 8/26/92 11:35 AM

**APPENDIX C**  
**SADDLE TANK FARM SITE SOIL GAS PERMEABILITY DATA**

TABLE C-1. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT G1-MPA

Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	4.0'	7.5'	11.0'		4.0'	7.5'	11.0'
0	0	0	0	16	3.6	3.5	5.9
1	2.5	2.6	5.1	18	3.4	3.4	5.9
2	3.0	3.0	5.5	20	3.4	3.4	5.9
3	3.1	3.2	5.6	22	3.4	3.4	6.0
4	3.1	3.2	5.7	24	3.4	3.4	6.0
5	3.2	3.3	5.7	26	3.4	3.5	6.0
6	3.4	3.4	5.8	28	3.4	3.5	6.0
7	3.4	3.4	5.8	30	3.4	3.5	6.0
8	3.4	3.4	5.9	40	3.4	3.5	6.0
9	3.5	3.5	5.9	50	3.4	3.5	6.0
10	3.4	3.4	5.9	60	3.4	3.5	6.0
12	3.4	3.4	5.9	90	3.5	3.5	6.0
14	3.4	3.4	5.9	120	3.4	3.5	6.0

TABLE C-2. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT GI-MPB


Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	4.0'	7.5'	11.0'		4.0'	7.5'	11.0'
0	0	0	<0.0	16	1.875	2.9	3.4
1	0.5	1.0	1.5	18	1.90	2.9	3.4
2	1.0	1.5	2.0	20	1.90	2.9	3.4
3	1.3	1.95	2.7	22	1.90	2.9	3.4
4	1.5	2.3	3.0	24	1.90	2.9	3.4
5	1.6	2.5	3.0	26	1.925	2.9	3.4
6	1.7	2.6	3.1	28	1.925	2.9	3.5
7	1.75	2.6	3.2	30	1.925	2.9	3.5
8	1.80	2.7	3.3	40	1.9	2.9	3.4
9	1.8	2.7	3.4	50	1.9	2.9	3.4
10	1.85	2.8	3.4	60	1.875	2.8	3.4
12	1.85	2.9	3.4	90	1.9	2.9	3.5
14	1.875	2.9	3.4	120	2.0	3.0	3.5

TABLE C-3. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT G1-MPC

Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	4.0'	7.5'	11.0'		4.0'	7.5'	11.0'
0	0	0	0	16	0.12	0.40	1.20
1	0.01	0.04	0.25	18	0.125	0.40	1.20
22.05	0.035	0.15	0.40	20	0.135	0.40	1.25
3.07	0.05	0.20	.50	22	0.130	0.40	1.25
4.0	0.065	0.20	0.70	24	0.130	0.40	1.25
5.0	0.08	0.25	0.80	26	0.130	0.40	1.25
6.0	0.09	0.25	0.90	28	0.130	0.40	1.30
6.55	0.10	0.30	0.95	30	0.135	0.42	1.30
8.0	0.11	0.35	1.0	40	0.130	0.40	1.30
9.0	0.12	0.35	1.05	50	0.125	0.40	1.25
10.16	0.12	0.35	1.10	60	0.120	0.40	1.20
12	0.13	0.35	1.15	90	0.130	0.40	1.30
14	0.12	0.40	1.20	120	0.125	0.40	1.25

**APPENDIX D**

**SADDLE TANK FARM SITE IN SITU RESPIRATION TEST DATA**



**Figure D-1. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G1-MPA-4.0'**







Figure D-2. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G1-MPA-7.5'



**Figure D-3. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G1-MPB-7.5'**




Figure D-4. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G1-MPC-11.0'

**APPENDIX E**

**POWER PLANT SITE SOIL GAS PERMEABILITY DATA**

TABLE E-1. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT G2-MPA

Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	3.0'	5.5'	8.0'		3.0'	5.5'	8.0'
0	0	0	<0	28.1	0.007	0.05	0.08
0.15	0	0.035	0.045	31	0.01	0.045	0.075
3	0	0.04	0.065	35	0.005	0.045	0.08
6	0	0.05	0.07	38.3	0.01	0.045	0.075
8.4	0.01	0.045	0.075	42	0.005	0.048	0.075
11.3	0	0.045	0.077	50	0.008	0.046	0.07
14.4	0.005	0.047	0.075	60	0.005	0.048	0.07
17.3	0.007	0.045	0.065	93	0.008	0.048	0.07
21	0.005	0.045	0.075	120.36	0.011	0.055	0.075
25	0.007	0.05	0.075				

TABLE E-2. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT G2-MPB

Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	3.0'	5.5'	8.0'		3.0'	5.5'	8.0'
0	0	0	<0	21	0.032	0.031	0.05
1	0.016	0.016	0.02	23	0.031	0.032	0.046
2	0.016	0.016	0.04	25	0.03	0.031	0.054
3	0.02	0.023	0.045	27	0.035	0.036	0.052
4	0.025	0.029	0.05	29	0.031	0.032	0.053
5	0.024	0.025	0.042	31	0.031	0.036	0.055
6	0.024	0.024	0.04	34	0.031	0.32	0.051
8	0.02	0.02	0.045	37	0.029	0.32	0.051
10	0.014	0.02	0.04	40	0.03	0.034	0.05
11	0.03	0.026	0.059	50	0.025	0.026	0.046
13	0.02	0.025	0.05	60	0.027	0.029	0.046
15	0.025	0.026	0.036	90	0.025	0.029	0.046
17	0.036	0.031	0.04	120	0.026	0.028	0.048
19	0.03	0.029	0.05				

TABLE E-3. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT G2-MPC

Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	3.0'	5.5'	8.0'		3.0'	5.5'	8.0'
0	<0	<0	<0	26.40	0.037	0.045	0.12
2	0.03	0.04	0.09	29.40	0.039	0.047	0.12
4	0.035	0.045	0.11	33	0.036	0.045	0.11
7	0.037	0.045	0.105	37	0.038	0.045	0.11
9.5	0.035	0.04	0.105	40	0.038	0.045	0.115
12.5	0.035	0.042	0.11	52	0.035	0.042	0.105
16	0.035	0.04	0.11	62	0.037	0.041	0.105
19	0.037	0.042	0.11	95	0.035	0.041	0.112
23.4	0.037	0.04	0.11	122.3	0.035	0.042	0.105

**TABLE E-4. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT G2-MPD**

Time (min)	Pressure ("H <sub>2</sub> O) by Depth		Time (min)	Pressure ("H <sub>2</sub> O) by Depth	
	2.0'	5.5'		2.0'	5.5'
0	0	0	18	0.009	0.010
1	0	0	20	0.010	0.010
2	0	0	22	0.005	0.005
3	0.005	0.005	24	0.010	0.010
4	0.015	0.010	26	0.015	0.010
5	0.015	0.010	28	0.015	0.015
6	0.010	0.015	30	0.015	0.020
7	0.010	0.015	33	0.010	0.020
8	0.010	0.010	36	0.010	0.010
9	0.010	0.010	39	0.005	0.010
10	0.010	0.010	50	0.005	0.010
12	0.009	0.010	60	0.010	0.005
14	0.005	0.010	90	0.005	0.010
16	0.010	0.005	120	0.010	0.010



**APPENDIX F**

**POWER PLANT SITE IN SITU RESPIRATION TEST DATA**







Figure F-1. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G2-MPA-10.0'



**Figure F-2. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G2-MPB-5.5'**



**Figure F-3. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G2-MPB-8.0'**



**Figure F-4. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G2-MPC-8.0'**

**APPENDIX G**

**MILLION GALLON HILL SITE SOIL GAS PERMEABILITY DATA**

TABLE G-1. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT G3-MPA

Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	10.0'	20.0'	27.5'		10.0'	20.0'	27.5'
0	0	0	<0	18	.005	0	9.5
1	<0	0	4.0	20	0.005	0.01	9.7
2.1	0	0	5.5	22	0.005	0.005	9.8
3	0.005	0	7.0	24	0.005	0.005	9.9
4	0.01	0.005	7.5	26	0.005	0.01	10.0
5	0.01	0.01	7.9	28	0.005	0.01	10.0
6	0.01	0.005	8.0	30	0.005	0.015	10.0
7.1	0.01	0.005	8.4	33	0.01	0.013	10.2
8.2	0.01	0.01	8.5	36	0.01	0.015	10.5
9.2	0.01	0.01	8.8	39	0.01	0.015	10.5
10	0.01	0.005	9.0	50	0.005	0.005	10.2
12	0.01	0.005	9.0	60	0.015	0.01	10.5
14	0.005	0.005	9.2	90	0.005	0.01	10.5
16	0.005	0.005	9.5	120	0.01	0.005	10.5

TABLE G-2. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT G3-MPB

Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	10.0'	20.0'	27.5'		10.0'	20.0'	27.5'
0	0	0	0	31	0.066	0.80	1.0
1	<0	<0	<0	34	0.079	0.85	1.10
3	<0	<0	<0	37	0.078	0.85	1.15
5	0	0.09	0.10	40	0.080	0.87	1.17
7	0	0.25	0.30	44	0.094	0.87	1.20
9	0	0.30	0.36	46	0.094	0.90	1.25
11	0.02	0.35	0.45	49	0.086	0.90	1.20
13	0.04	0.45	0.55	52	0.086	0.90	1.20
15	0.05	0.50	0.65	56	0.086	0.95	1.25
17	0.05	0.55	0.75	57	0.086	0.94	1.20
20	0.056	0.65	0.85	59	0.084	0.94	1.25
22	0.057	0.70	0.90	75	0.084	0.94	1.20
25	0.07	0.75	0.95	90	0.083	0.94	1.20
29	0.069	0.77	0.96	120	0.083	0.94	1.20




TABLE G-3. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT G3-MPC


Time (min)	Pressure ("H <sub>2</sub> O) by Depth		Time (min)	Pressure ("H <sub>2</sub> O) by Depth	
	10.0'	20.0'		10.0'	20.0'
0	0	0	33	0	0.02
2	0	0	36	0	0.02
4	0	0	39	0	0.02
5	0	0	43	0	0.02
8	0	0	45	0	0.02
10	0	0	55	0	0.02
12	0	0	75	0	0.018
14	0	0	90	0	0.019
16	0	0	120	0	0.019
19	0	0			
22	0	0			
24	0	0.01			
27	0	0.015			
30	0	0.015			

**APPENDIX H**


**MILLION GALLON HILL SITE IN SITU RESPIRATION TEST DATA**



**Figure H-1. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G3-MPA-20.0'**



**Figure H-2. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G3-MPA-27.5'**



**Figure H-3. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G3-MPB-20.0'**




Figure H-4. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point G3-MPB-27.5'

**APPENDIX I**

**CAMPION POL TANK SITE SOIL GAS PERMEABILITY DATA**

TABLE I-1. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT CA-MPA

Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	3.0'	5.0'	7.0'		3.0'	5.0'	7.0'
0	0	0	0	17	0.140	1.65	1.85
1	0.130	1.80	2.1	18	0.135	1.65	1.85
2	0.140	1.75	2.1	20	0.135	1.65	1.85
3	0.135	1.75	2.1	22	0.132	1.60	1.80
4	0.140	1.70	1.85	24	0.131	1.60	1.80
5	0.135	1.60	1.80	26	0.131	1.60	1.80
7	0.140	1.55	1.75	28	0.131	1.60	1.77
8	0.125	1.50	1.70	30	0.127	1.55	1.77
9	0.120	1.45	1.60	60	0.130	1.55	1.77
12	0.110	1.35	1.60	90	0.127	1.55	1.75
14	0.140	1.60	1.75				



TABLE I-2. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT CA-MPB


Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	3.0'	5.0'	7.0'		3.0'	5.0'	7.0'
0	0	0	0	16	0.061	0.069	0.082
1	0.06	0.074	0.088	19	0.062	0.068	0.08
3	0.064	0.071	0.086	21	0.06	0.064	0.079
5	0.064	0.069	0.081	23	0.059	0.065	0.079
6	0.06	0.069	0.08	24	0.059	0.065	0.079
8	0.059	0.061	0.08	25	0.059	0.065	0.079
10	0.059	0.064	0.075	27	0.056	0.064	0.079
11	0.055	0.06	0.07	29	0.056	0.064	0.079
12	0.053	0.058	0.069	60	0.061	0.069	0.084
14	0.051	0.057	0.067	90	0.061	0.068	0.084

TABLE I-3. RESULTS OF SOIL GAS PERMEABILITY TEST AT MONITORING POINT CA-MPC


Time (min)	Pressure ("H <sub>2</sub> O) by Depth			Time (min)	Pressure ("H <sub>2</sub> O) by Depth		
	3.0'	5.0'	7.0'		3.0'	5.0'	7.0'
0	0	0	0	18	0.041	0.041	0.041
2	0.039	0.04	0.04	20	0.041	0.041	0.041
4	0.04	0.041	0.041	22	0.041	0.041	0.041
5	0.041	0.041	0.041	23	0.041	0.041	0.041
7	0.041	0.041	0.041	24	0.041	0.041	0.041
9	0.041	0.041	0.041	28	0.041	0.041	0.041
10	0.04	0.04	0.04	30	0.041	0.041	0.041
12	0.04	0.04	0.04	62	0.041	0.041	0.041
13	0.039	0.038	0.038	90	0.041	0.041	0.041
14	0.039	0.041	0.041				

**APPENDIX J**


**CAMPION POL TANK SITE IN SITU RESPIRATION TEST DATA**




**Figure J-1. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point C1-MPA-7.0'**



**Figure J-2. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point C1-MPB-5.0'**



**Figure J-3. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point C1-MPB-7.0'**



**Figure J-4. Oxygen Utilization and Carbon Dioxide Production During the In Situ Respiration Test at Monitoring Point C1-MPC-5.0'**